

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

For corners in

LAPEER
(County)

Located In:
Imlay Twp.

Corner Code #

1. Public Land Survey

T 7N R 12E

M-13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD
94 JAN -5 PM 1:34
LIBER NO 005 PAGE NO. 83
Melissa Miles
SECRETARY OF STATE
MICHIGAN
(79)
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K
2											
3											
4											
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

John C. Niederhauser, in a field survey on Nov. 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Post (G.L.O. Notes, pg. 560) No bearing trees noted
40 ch North to 1/2 mile post Section 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Re-Rod
NE to P.K. in S.W. side P. pole 64.52'
SW to nail & MDSH tag in anchor post 44.47'
2644.38' North to E 1/4 corner Section 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass disk stamped "Lapeer County Remonumentation M-13 #24608"
NW to P.K. w/tag in west end 18" CSP 34.74'
SW to nail w/tag in NW side G.T.E. pole 44.34'
NE to nail w/tag in SW side P. pole 64.52'
NE to nail w/tag in W face 8" wood post 46.30'



Signed by *John C. Niederhauser* Date Dec. 30, 1993
Surveyor's Michigan License No. 24608