

SURVEY & REMONUMENTATION

REMONUMENTATION

RECEIVED FOR RECORD

MAR 23 2000

LAND CORNER RECORDATION CERTIFICATE

00 FEB 10 PM 2:15

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

LAPEER
(County)

Located In:
OREGON TWP

Corner Code #

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

474

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>8</u> N	R <u>9</u> E	<u>A-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MICHAEL G. HAY, in a field survey on AUGUST 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1822- JOSEPH WAMPLER D.S. SET POST FOR TOWN 7 & 8 NORTH-RANGE 9 EAST
1866- GILBERT BATES C.S. STONE 16 12 6 CROCKERY SMALL STONES
1985- HAROLD N. ELRICH P.S. 18986 (SURVEY) LIBER 7 PAGE 37
1978- DONALD G. RICHARDS P.S. 24614 (UNRECORDED) FOUND 3/4" IRON
1997- RAY D. DAVIS P.S. 22430 (UNRECORDED) FOUND 5/8" IRON
1997- CHARLES T. LILLIEBERG P.S. 40162 (SURVEY) LIBER12, PAGE 469 FOUND 3/8" IRON IN MON BOX

DEED GROUP
APPROVED LAND CORNER
BOOK OF 1990
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-2-1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999- MICHAEL G. HAY P.S. 41101 FOUND 5/8" IRON IN MON BOX IN CENTERLINE OF OREGON AND WASHBURN ROADS.
A-13 TO B-13 2127.01' (M) 2126.83' (HBE) 2475.00 (37.50 GLO)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD REMONUMENTATION CAP ON 1/2" IRON IN MONUMENT BOX
- WEST 30.79 TAG 40162 IN NORTH FACE OF 12" TWIN CHERRY
- S 45 E 59.46' TAG 40162 IN NORTHEAST FACE OF 18" SCOTCH PINE
- N 30 E 67.86' TAG 40162 IN SOUTHEAST FACE OF POWER POLE
- N 65 E 72.32' TAG 40162 IN SOUTH FACE OF 30" MAPLE

STATE OF MICHIGAN
MICHAEL G. HAY
PROFESSIONAL SURVEYOR
No. 41101
LICENSED PROFESSIONAL SURVEYOR

CORNER IS COMMON TO A-1, T7N-R9E, ELBA TOWNSHIP

Signed by Michael G. Hay Date 1-11-2000
Surveyor's Michigan License No. 41101