

SURVEY &  
REMONUMENTATION

MAR 23 2000

REMONUMENTATION

SECTION \_\_\_\_\_ LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 FEB 10 PM 2:17

For corners in

LAPEER Located In: OREGON TWP. Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 8 N R 9 E C-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Melissa De Vaughn*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

**477**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MICHAEL G. HAY, in a field survey on AUGUST 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1822- JOSEPH WAMPLER D.S. SET POST CORNER SECTION 31 & 32  
1974- HAROLD N. ELRICH P.S. 18986 (SURVEY) LIBER 2 PAGE 846 FOUND 1/2" IRON  
1982- HAROLD N. ELRICH P.S. 18986 (SURVEY) LIBER 6 PAGE 413 FOUND 1/2" IRON  
1983- BERNARD HENERSON P.S. 16043 (SURVEY) LIBER 6 PAGE 613  
1984- HAROLD N. ELRICH P.S. 18986 (SURVEY) LIBER 6 PAGE 910 FOUND 1/2" IRON  
1997- EARL E. GRAVLIN P.S. 23510 (SURVEY) LIBER 12 PAGE 207 FOUND 1/2" IRON IN MON BOX

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 12-2-1999

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999 MICHAEL G. HAY P.S. # 41101 FOUND 1/2" IRON IN MON BOX, 4' NORTH OF CENTER LINE OF OREGON ROAD AND ON CENTER LINE OF ELBA ROAD EXTENDED SOUTH FROM THE NORTH.  
C-13 TO D-13 2637.98' (M) 2640.00' (40 GLO)  
C-13 TO B-13 2626.44' (M) 2626.31' (GRAVLIN) 2640.00' (40 GLO)  
C-13 TO C-1 EAST 112.64' (M) 112.86' (171 GLO)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD REMONUMENTATION CAP ON 1/2" IRON IN MON BOX  
S 20 E 52.29' NAIL IN WEST FACE POWER POLE  
S 45 W 8.98' CHISELED "X" ON NE EDGE OF MANHOLE RIM  
N 10 W 160.53' NAIL IN WEST FACE OF POWER POLE  
N 45 W 44.96' SPIKE IN EAST FACE OF 15" TWIN POPLAR



Signed by Michael G. Hay Date 1-11-2000

Surveyor's Michigan License No. 41101

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971