

MAR 29 1999

SECTION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 JAN -6 PM 1:40

For corners in

LAPEER (County)

Located In: OREGON TWP.

Corner Code #

K-2

Melissa D. Vaughn REGISTER OF DEEDS LAPEER COUNTY, MICHIGAN

445

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 8 R 9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 1-13. Values include 6, 5, 4, 3, 2, 7, 8, 9, 10, 11, 18, 17, 16, 15, 14, 19, 20, 21, 22, 23, 30, 29, 28, 27, 26, 31, 32, 33, 34, 35.

I, MICHAEL G. HAY, in a field survey on MARCH 3 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1821-JOSEPH WAMPLER D.S. SET POST AT 40 CHAINS W. OAK 30 WEST 22 B. ASH 10 N40E 8
1864-GILBERT BATES C.S. STAKE ELM 22 N13E WHITE OAK ORIGINAL
1974-ROBERT G. KAY P.S. 14096 L3 P1 FOUND RE-ROD
N80W 23.83' 8" TRIPLE ASH
N60E 33.63' 20" OAK
N85E 23.10' 15" OAK
1975-ROBERT G. KAY P.S. 14096 L3 P289 (SAME AS 1974 TIES)
1975-BERNARD HENDERSON P.S. 16043 L2 P133 (SAME AS 1974 TIES)
1976-LELAND D. BATES P.S. 16699 L3 P828 (SAME AS 1974 TIES)
1995-EARL E. GRAVLIN P.S. 23510 L11 P649 FOUND 1/2 IRON
N80W 23.72' N/S 8" ASH
N45E 33.55' N/S 36" OAK
N80E 23.07' N/S 24" OAK
1997-RAY D. DAVIS P.S. 22430 L0011 P0971 (SAME AS 1995 TIES)

GROUP RECORDED CORNER

Signature and date 9-17-98

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1998 MICHAEL G. HAY P.S. 41101 FOUND 1/2" IRON ROD IN CENTER LINE OF FLINT RIVER ROAD FIC # 18986 33' WEST OF THE WEST COR OF SECTION 1 ALSO FOUND DOWNED FENCE LINE TO EAST, RECOVERED THREE WITNESSES CLOSE IN RECORDED DISTANCES.
K-2 TO K-1 3110.35 (M) 3110.42 (R-HBE)
K-2 TO K-3 2641.26 (M) 2641.27 (R-HBE) 40 (GLO-2640.00)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-2 SET STANDARD REMONUMENTATION CAP ON FOUND 1/2" IRON
N80W 23.79' 9" TRIPLE ASH FND P.K. IN N FACE
N45E 33.63' 26" OAK FND NAIL IN BOTTLE CAP NW FACE
N80E 23.15' 18" OAK FND P.K. NORTH FACE
S40W 47.06' 28" OAK SET NAIL IN SE FACE

Signed by Michael S Hay Date 12-30-98
Surveyor's Michigan License No. 41101

