

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 JAN -6 PM 1:40

For corners in

LAPEER Located In: OREGON TWP. (County)

Corner Code #

Melissa DeVaugh REGISTER OF DEEDS LAPEER COUNTY, MICHIGAN

446

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 8 R 9 K-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, MICHAEL G. HAY, in a field survey on MARCH 3, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Values include 6, 5, 4, 3, 2, 1, 7, 8, 9, 10, 11, 12, 18, 17, 16, 15, 14, 13, 19, 20, 21, 22, 23, 24, 30, 29, 28, 27, 26, 25, 31, 32, 33, 34, 35, 36.

A. Description of original monument and accessories and/or subsequent restoration:

- 1821-JOSEPH WAMPLER DS SET POST BIRCH 14 N4E 25 DO 15 S89E 21
1864-GILBERT BATES CS STAKE CEDAR 24 N301/4W 78 CEDAR 24 S34W 74 ORIGINAL BEECH 16 S60 1/2E 19
1972-SHELDON R. BROWN P.S. 17613 L001 P705 (SET NAIL)
1974-ROBERT G. KAY P.S. 14096 L2 P579 FOUND 1/2" REROD EAST 23.02' FENCE POST S40W 46.99' 8" ELM N35W 53.1' BELL MARKER
1974-HAROLD N. ELRICH P.S. 18986 L3 P28 FOUND 1/2" IRON EAST 23.0' CORNER POST WEST 23.53' CORNER POST
1976-HAROLD N. ELRICH P.S. 18986 L3 P857 FOUND 1/2" IRON EAST 23.00' CORNER POST WEST 23.53' CORNER POST N30W 47.36' 6" POPLAR

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998-MICHAEL G. HAY P.S. 41101 FOUND 1/2" IRON IN MON BOX 3'+/- WEST OF CENTER LINE OF FLINT RIVER ROAD. FENCE LINE RUNNING WEST. RECOVERED 33' R.O.W. 1 ROWS FROM SURVEY BY EARL GRAVLIN.

K-3 TO K-2 2641.26' (M) 2641.27' (R-HBE)
K-3 TO K-4 2634.09' (M) 2634.83' (R-KAY) 2634.03' (R-HBE) 2634.03 (R-GRAVLIN)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 SET STANDARD REMONUMENTATION CAP ON FOUND 1/2" IN MONUMENT BOX EAST 33.12' FIC #23510 N40E 46.47' CUT "V" IN 15" C.M.P. WEST 33.10' FIC #23510 NORTH 1/2" IRON IN MONUMENT BOX .3'+/- WEST OF CENTER LINE OF FLINT RIVER ROAD



Signed by Michael G. Hay Date 12-30-98

Surveyor's Michigan License No. 41101

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975 REVISED JAN., 1983 ADAPTED FOR WORD PROCESSING MARCH, 1993

MAR 29 1999

SECTION

1976-LELAND D. BATES P.S. 16699 L3 P828 FOUND ½" ROD EAST 19.97' FENCE POST
S40W 46.99' 8" ELM
N35W 53.1' BELL MARKER

1977-KENNETH D. DUNTON P.S. 23503 LAND CORNER-RECORDATION CERTIFICATE L003 P318 FND ½" REROD
S40E 46.99' NAIL IN 8" ELM
EAST 19.97' NAIL IN FENCE POST
N35W 53.12' TOP OF BURIED CABLE MARKER

1978-BERNARD HENDERSON P.S. 16043 L4 P708 FOUND ½" IRON EAST 19.97' FENCE POST
S40W 46.99' 8" ELM

1978-HAROLD N. ELRICH P.S. 18986 L5 P77 FOUND ½" IRON EAST 19.97' FENCE POST
S40W 46.99' 8" ELM
N35W 53.1' BELL BOX

1979-JAMES A. BECK P.S. 21559 L005 P337 EAST 19.97' FENCE POST
S40W 46.99' 8" ELM

1989-RUSSELL L. BROWN P.S. 24588 FOUND ½" ROD EAST 19.97' FENCE POST
S40W 46.99' 8" ELM
N35W 53.1' BELL MARKER

1991-EARL E. GRAVLIN P.S. 23510 L009 P557 FOUND ½" IRON EAST 19.37' FENCE POST
S40W 46.99' 8" ELM
N35W 53.1' BELL BOX

1993-EARL E. GRAVLIN P.S. 23510 L010 P257 REPLACED ½" IRON FROM OLD SURVEYS
EAST 33.0' ½" IRON & CAP
S85E 3.33' IRON MON BOX
NORTH 157.6' MON BOX

1993-EARL E. GRAVLIN P.S. 23510 L010 P447 FOUND ½" IRON IN MON BOX
EAST 33.0' ½" IRON
WEST 33.0' ½" IRON
NORTH 157.6' MON BOX

1994-RAY D. DAVIS P.S. 22430 L0010 P0818 FOUND NAIL SET IN SURVEYS RECORDED IN L001 P705

1994-EARL E. GRAVLIN P.S. 23510 FOUND ½" IRON IN MON BOX EAST 33.0' ½" IRON
WEST 33.0' ½" IRON
NORTH 157.6' MON BOX

1995-EARL E. GRAVLIN P.S. 23510 L4 P649 FOUND ½" IRON EAST 33.0' ½" IRON
S85E 3.33' IRON IN MON BOX
N 157.60' MON BOX

1997-RAY D. DAVIS P.S. 22430 L0011 P0973 FOUND ½" IRON IN MON BOX EAST 33.0' FOUND ½" IRON
S85E 3.33' FOUND IRON IN MON BOX
NORTH 157.60' FOUND IRON IN MON BOX
WEST 33.0' FOUND IRON

PEER GROUP
APPROX. CORNER

DATE 9-17-98

MISC 9.00
REMLC P0075
REMOVT 2.00