

RECORDS SECTION

MAR 29 1999

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 JAN -6 PM 1:43

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

For corners in SECTION

LAPEER

Located In:
OREGON TWP.

Corner Code #

448

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 8 R 9 L-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, MICHAEL G. HAY, in a field survey on MARCH 3 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- NO CORNER SET ORIGINAL SURVEY
- 1974-HAROLD N. ELRICH P.S. 18986 L3 P28 SET 1/2" IRON ROD
S85W 52.82' SET NAIL 18" MAPLE
N48E 40.0' SW COR. GARAGE
S15E 32.98' SET NAIL 30" OAK
- 1976-HAROLD N. ELRICH P.S. 18986 L3 P857 FOUND 1/2" IRON ROD (SAME AS 1974 TIES)
- 1993-EARL E. GRAVLIN P.S. 23510 L10 P257 (SAME AS 1974 TIES)
- 1994-RAY D. DAVIS P.S. 22430 L0010 P0818 (SAME AS 1974 TIES)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998-MICHAEL G. HAY P.S. 41101 FOUND 5/8" SMOOTH BAR 142+/- SOUTH OF CENTER LINE MCKEEN LAKE ROAD 33'+/- EAST OF CENTER LINE DRIVE OF CAMP O' FAIR WINDS, TREE LINE RUNNING TO THE SOUTH RECOVERED 3 WITNESSES CLOSE IN RECORDED MEASURED DISTANCES.

- L-4 TO M-4 2645.86 (M) 2645.90 (R-HBE)
- L-4 TO K-4 2653.37 (M) 2653.32 (R-HBE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-4 SET STANDARD REMONUMENTATION CAP AND 1/2" IRON ROD (REPLACED 5/8" IRON)
- S85W 52.77' 21" MAPLE RESET NORTH FACE
- N40E 40.00' SW COR GARAGE HSE #3279
- S15E 33.00' 36" OAK RESET NAIL IN NE FACE
- N45W 68.39' 14" TWIN OAK RESET NAIL NORTH FACE

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

LAPEER COUNTY
MICHAEL G. HAY
PROFESSIONAL SURVEYOR
DATE 9-17-98



Signed by Michael G. Hay Date 12-30-98

Surveyor's Michigan License No. 41101

a'