

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

LAPEER Located In: _____ Corner Code #
County:

1. Public Land Survey T 8N R 9E _____ M-4
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD

95 OCT -6 PM 1:11

LIBER NO. 005 PAGE NO. 289

Melissa Z. Laugh

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, HAROLD N. ELRICH, in a field survey on AUGUST 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1822 WAMPLER D.S. SET 1/2 MILE POST - PINE N 24 1/2° W 50 LINKS, ELM 17" S 84 1/2° W 38 LINKS
1974 ELRICH P.S. LAND CORNER RECORDATION CERTIFICATE - LIBER 002, PAGE 693 FOUND 1/2" IRON N 15° E 53.29 FEET 30" OAK, N 35° W 58.76 FEET 8" TREE, S 75° W 32.25 FEET 8" LOCUST
1974 ELRICH P.S. (SURVEY) LIBER 003, PAGE 028 - FOUND 1/2" IRON - SAME WITNESSES AS 1974 LAND CORNER RECORDATION CERTIFICATE
1976 ELRICH P.S. (SURVEY) LIBER 003, PAGE 857 - FOUND 1/2" IRON - SAME WITNESSES AS 1974 LAND CORNER RECORDATION CERTIFICATE
1990 ELRICH P.S. (UNRECORDED SURVEY) - RESET 1/2" IRON USING WITNESSES FROM 1974 LAND CORNER RECORDATION CERTIFICATE - N 15° E 52.96 FEET NAIL-30" OAK, S 75° W 32.71 FEET NAIL-8" CALTALPA, N 75° E 22.40 FEET NAIL-6" ELM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 ELRICH P.S. FOUND 1/2" IRON ON WEST EDGE OF ONE LANE TRAIL. TOP OF IRON AT GROUND LEVEL. THERE IS A FENCE RUNNING NORTH APPROXIMATELY 90 FEET - NORTH OF M-4. FOUND TWO WITNESSES FROM PREVIOUS SURVEYS THAT LOCATE 1/2" IRON FOUND. MEASUREMENT TO L-4 MATCHED PREVIOUS SURVEY.

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF EAST 1/4 CORNER OF SECTION 22, T8N-R9E, OREGON TOWNSHIP, LAPEER COUNTY, MICHIGAN

MEASURED REFERENCES - M-4 TO M-3 2640.06 FEET
M-4 TO M-5 2659.45 FEET
M-4 TO L-4 2645.73 FEET

PEER GROUP
APPROVED LAND CORNER
PAGE 289 OF 1990
LAPEER COUNTY
Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 8-31-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 PLACED LAPEER COUNTY REMONUMENTATION CAP ON 1/2" IRON FOUND

SET NEW WITNESSES - N 35° W 55.80 FEET P.K. NAIL & WASHER IN 6" ELM
N 15° E 53.08 FEET P.K. NAIL & WASHER IN 30" OAK
S 35° W 26.04 FEET P.K. NAIL & WASHER IN 6" ELM
S 75° W 32.67 FEET P.K. NAIL & WASHER IN 8" LOCUST
NORTH 91.71 FEET 1/2" PIPE WEST 1/4 CORNER, SEC. 7, T8N-R10E

MAYFIELD TOWNSHIP

Signed by *Harold N. Elrich* Date 9/26/95
Surveyor's Michigan License No. 18986