

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PH 1:48

LIBER NO. 05 PAGE NO. 107-108  
*Walter DeWitt*  
 REGISTERED SURVEYOR  
 LAPEER COUNTY MICHIGAN

For corners in <u>LAPEER</u> County	Located in: OREGON TWP	Corner Code # <u>M-6</u>
1. Public Land Survey	T <u>8N</u> R <u>9E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH, in a field survey on AUG 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
 1824 SYLVESTER SIBLEY D.S. SET 1/2 MILE POST WHITE OAK 32" N 31° W 34 LINKS,  
 PINE 30" N 63° W 28 LINKS  
 1868 GILBERT BATES STAKE -PINE STUMP 30" S 72 1/2° W 55 LINKS, PINE 34" N 58 1/2° W 115 LINKS  
 1972 ELRICH P.S. LAND CORNER RECORDATION CERTIFICATE LIBER 001, PAGES 185 & 186  
 N 30° W 47.65 FEET NAIL IN 10" MAPLE S 50° W 39.00 FEET 12" OAK  
 1975 HENDERSON P.S. LIBER 001, PAGE 532 FOUND P.K. NAIL (TIES MATCH 1972 LAND CORNER RECORDATION CERTIFICATE)  
 1976 BATES P.S. LIBER 003, PAGE 576 FOUND P.K. NAIL (TIES MATCH PREVIOUS SURVEYS)  
 1976 HENDERSON P.S. LIBER 003, PAGE 504 NO OBJECT STATED CORNER IS SOUTH 95.95 FEET FROM WEST 1/4 CORNER, SEC 18, T8N-R10E, MAYFIELD TWP (TIES MATCH PREVIOUS SURVEYS) (SEE BACK)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 ELRICH P.S. FOUND 1/2" IRON ROD IN MONUMENT BOX 0.50 FEET EAST OF CENTERLINE OF MILLVILLE ROAD. FENCE AND TREE LINE RUNNING WEST OF FOUND CORNER. MEASURED NORTH 90.95 FEET TO WEST 1/4 CORNER OF SECTION 18, T8N-R10E, MAYFIELD TOWNSHIP. FOUND TWO WITNESSES FROM PREVIOUS SURVEYS THAT VERIFIED LOCATION OF FOUND 1/2" IRON ROD.

ACCEPTED FOUND 1/2" IRON ROAD IN MONUMENT BOX AS BEST LOCATION OF ORIGINAL POSITION OF EAST 1/4 CORNER OF SECTION 13, T8N-R9E, OREGON TOWNSHIP

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 SET STANDARD REMONUMENTATION CAP OVER FOUND 1/2" IRON ROAD

NAIL & WASHER	10" HICKORY	N 30° E	71.48 FEET
NAIL & WASHER	23" CHERRY	N 80° W	67.85 FEET
NAIL & WASHER	28" MAPLE	S 30° W	58.04 FEET
NAIL & WASHER	20" OAK	S 70° W	38.74 FEET

Signed by Harold N. Elrich

Date NOV 3, 1994

Surveyor's Michigan License No. 18986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 29, 1975  
 REVISED MAY 14, 1979  
 LANSING, MICHIGAN 48103

A (CONTINUED)

1980 BECK P.S. LIBER 005, PAGE 779 FOUND P.K. NAIL (TIES MATCH PREVIOUS SURVEY)

1983 ELRICH P.S. LIBER 006, PAGE 612 NO OBJECT STATED  
 S 70° W 38.74 FEET P.K. IN 18" OAK  
 N 88° W 31.29 FEET TELEPHONE POLE  
 N 88° E 27.43 FEET TELEPHONE POLE  
 N 30° W 47.46 FEET NAIL IN 12" MAPLE

1986 ELRICH P.S. LIBER 007, PAGE 340 NO OBJECT STATED (TIES MATCH 1972 LAND CORNER RECORDATION CERTIFICATE)

1986 ELRICH P.S. UNRECORDED FOUND P.K. NAIL (TIES SAME AS 1972 LAND CORNER RECORDATION CERTIFICATE)

1988 GRAVLIN P.S. LIBER 007, PAGE 996 & 997 NO OBJECT STATED  
 (TIES MATCH 1972 LAND CORNER RECORDATION CERTIFICATE)

1988 ELRICH P.S. LIBER 008, PAGE 054 FOUND P.K. NAIL  
 N 50° W 38.74 FEET 22" OAK, N 30° W 47.46 FEET 12" MAPLE,  
 N 88° W 31.29 FEET TELEPHONE POLE, WEST 32.95 FEET 1/2" IRON ROD

PREPARED BY  
 APPROVED BY \_\_\_\_\_

RAY DAVIS, SURVEYOR  
 DATE 11-18-94

MISC D	9.00
REMLC	PO075
REMONT	2.00