

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:47

LIBER NO. 05 PAGE NO. 105-
HAROLD N. ELRICH
REGISTERED PROFESSIONAL SURVEYOR
LAPEER COUNTY MICHIGAN

For corners in
LAPEER County

Located In: OREGON TWP Corner Code ## M-7

1. Public Land Survey	T <u>8N</u> R <u>9E</u>	<u>M-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on AUG 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1824 GLO SYLVESTER SIBLEY DS. SET POST COMMON TO SECTIONS 13 & 24
WHITE OAK 36" N 43" W 12 LINKS WHITE OAK 36" S 26° W 72 LINKS
- 1868 GILBERT BATES STONE 18,11, 6 EARTHEN SMALL STONES ELM 9" N 69° W 99 LINKS
ELM 6" S 26° W 84 LINKS
- 1972 HENDERSON P.S. LIBER 001, PAGES 379 & 380 LAND CORNER RECORDATION CERTIFICATE
SET NAIL BETWEEN RIGHT OF WAY FENCES AT CENTERLINE OF MILLVILLE ROAD
S 35° E 45.20 FEET 20" MAPLE, S 45° W 40.35 FEET ROAD SIGN
N 60° W 50.30 FEET 24" OAK (SEE BACK)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 ELRICH P.S. FOUND 1/2" IRON ROD IN MONUMENT BOX 1.5 FEET EAST OF CENTERLINE OF MILLVILLE ROAD ON CENTERLINE OF FLINT RIVER ROAD. MEASURED 73.18 FEET NORTH TO IRON IN MONUMENT BOX USED FOR SOUTHWEST CORNER OF SECTION 18, T8N-R10E, MAYFIELD TOWNSHIP. GLO PLAT INDICATES 111 LINKS (73.26 FEET) BETWEEN THESE CORNERS. RECOVERED FOUR WITNESSES FROM PREVIOUS SURVEYS THAT MATCH LOCATION OF 1/2" IRON ROD FOUND. ACCEPTED 1/2" IRON ROD FOUND AS BEST LOCATION OF ORIGINAL POSITION OF NORTHEAST CORNER OF SECTION 24, T8N-R9E, OREGON TOWNSHIP
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- M-7 SET STANDARD REMONUMENTATION CAP OVER FOUND 1/2" IRON ROD
- | | | | |
|---------------|-----------------|---------|-------------|
| NAIL & WASHER | POWER POLE | S 70° W | 78.70 FEET |
| NAIL & WASHER | 24" MAPLE | S 35° E | 42.14 FEET |
| NAIL & WASHER | 24" MAPLE | N 88° E | 34.20 FEET |
| NAIL & WASHER | 10" ELM | N 75° W | 112.36 FEET |
| 1/2" IRON | IN MONUMENT BOX | NORTH | 73.26 FEET |

Signed by Harold N. Elrich Date NOV 3, 1994
Surveyor's Michigan License No 18986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 1987, REVISED MAY 1988



A. (CONTINUED)

- 1975 HENDERSON P.S. LIBER 003, PAGE 197 FOUND 1/2" IRON
S 35° E 44.02 FEET 20" MAPLE N 60° W 51.48 FEET 18" BOX ELDER
S 70° E 70.88 FEET SOUTHWEST CORNER HOUSE
- 1975 HENDERSON P.S. LIBER 003, PAGE 462 FOUND 1/2" IRON (SAME TIES AS PREVIOUS SURVEY)
- 1979 HENDERSON P.S. LIBER 005, PAGE 999 NO OBJECT STATED
N 60° W 50.3 FEET 24" OAK S 45° W 40.35 FEET ROAD SIGN
S 35° E 45.2 FEET 20" MAPLE
- 1980 HENDERSON P.S. LIBER 005, PAGE 720 NO OBJECT STATED
NORTH 73.18 FEET SOUTHWEST CORNER SECTION 18, T8N-R10E, MAYFIELD TOWNSHIP
N 45° W 44.78 FEET ROAD SIGN S 70° E 44.10 FEET 24" MAPLE
S 70° W 78.65 FEET POWER POLE
- 1981 ELRICH P.S. LIBER 006, PAGE 324 FOUND P.K. NAIL (SAME TIES AS 1980 SURVEY)
- 1983 ELRICH P.S. LIBER 006, PAGE 612 NO OBJECT STATED
N 88° E 34.20 FEET P.K. NAIL 24" MAPLE S 45° E 44.02 FEET NAIL 24" MAPLE
S 75° W 78.70 FEET P.K. NAIL POWER POLE S 75° E 70.90 FEET SOUTHWEST CORNER
OF HOUSE
- 1986 ELRICH P.S. LIBER 007, PAGE 340 NO OBJECT STATED
SOUTH 73.18 FEET FROM SOUTHWEST CORNER OF SECTION 18, T8N-R10E, MAYFIELD TOWNSHIP
- 1986 ELRICH P.S. UNRECORDED FOUND 1/2" IRON SOUTH 35° E 44.02 FEET 20" MAPLE
N 60° W 51.48 FEET 24" OAK N 45° E 64.08 FEET 18" BOX ELDER
S 70° E 70.88 FEET SOUTHWEST CORNER OF HOUSE
- 1988 ELRICH P.S. LIBER 008, PAGE 054 FOUND 1/2" IRON S 70° W 78.70 FEET
POWER POLE S 75° E 70.90 FEET SOUTHWEST CORNER OF HOUSE
S 35° E 42.21 FEET 20" MAPLE
- 1989 GRAVLIN P.S. LIBER 008, PAGE 559 FOUND P.K. NAIL (TIES MATCH PREVIOUS SURVEY)
- 1989 GRAVLIN P.S. LIBER 008, PAGE 716 NO OBJECT STATED (SAME TIES AS PREVIOUS SURVEY)

RESPECTFULLY
APPROVED BY SURVEYOR
RAY DAVIS

RAY DAVIS
DATE 11.12.94

MISC D 9.00
REMLC P0075
REMOVT 2.00