

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:46

LIBER NO. 65 SERENO 163

Michael DeLuca 104
REGISTER OF DEEDS
LAPEER COUNTY MICHIGAN

| | | |
|---|-------------------------|----------------|
| For corners in | Located in: | Corner Code ## |
| <u>LAFEEER</u> <small>County</small> | <u>OREGON TOWNSHIP</u> | |
| 1. Public Land Survey | T <u>8N</u> R <u>9E</u> | <u>M-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____ Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on AUG 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1824 GLO SYLVESTER SIBLEY D.S. WHITE OAK 30" S 05° W 28 LINKS, PINE 32" N 48° W 28 LINKS
 1875 GILBERT BATES STONE 23,11,7 SMALL STONES
 1977 ELRICH P.S. LAND CORNER RECORDATION CERTIFICATE LIBER 003, PAGE 323 FOUND 1/2" IRON S 45° W 48.22 FEET TELEPHONE POLE, S 30° E 67.63 FEET TELEPHONE POLE, N 30° E 70.66 FEET 36" OAK
 1978 BATES P.S. LIBER 005, PAGE 34 (TIES MATCH 1977 LAND CORNER RECORDATION CERTIFICATE)
 1979 ELRICH P.S. LIBER 005, PAGE 551 FOUND 1/2" IRON, S 45° W 48.32 FEET TELEPHONE POLE, S 30° E 67.63 FEET TELEPHONE POLE, N 30° E 70.66 FEET 36" OAK, NORTH 22.47 FEET 1/2" IRON (SEE BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 ELRICH P.S. FOUND 1/2" IRON ROD IN MONUMENT BOX 2.0 FEET WEST OF CENTERLINE OF MILLVILLE ROAD ON THE CENTERLINE OF BOLTON ROAD TO THE WEST. FOUND FOUR WITNESSES FROM PREVIOUS SURVEYS THAT MATCH FOUND 1/2" IRON ROD. MEASURED NORTH 22.33 FEET TO NORTHEAST CORNER OF SECTION 30, T8N-R10E, MAYFIELD TOWNSHIP (A-9) ORIGINAL GLO PLAT INDICATES 34 LINKS (22.44 FEET) BETWEEN THESE TWO CORNERS

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHEAST CORNER OF SECTION 24, T8N-R9E, OREGON TOWNSHIP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 SET STANDARD REMONUMENTATION CAP OVER FOUND 1/2" IRON ROD
 SET NAIL & WASHER S 35° E 42.54 FEET 8" ELM
 SET NAIL & WASHER N 30° E 70.66 FEET 36" OAK
 SET NAIL & WASHER N 80° E 36.10 FEET TOP FENCE POST
 1/2" IRON IN MONUMENT BOX NORTH 22.33 FEET

Signed by Harold N. Elrich
 Surveyor's Michigan License No. 18986

Date 7/27, 3, 1994


FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS



A. (CONTINUED)

1988 DAVIS P.S. LIBER 004, PAGE 162 FOUND 1/2" IRON (TIES SAME AS 1977 LAND CORNER RECORDATION CERTIFICATE)

1989 GRAVLIN P.S. LIBER 008, PAGE 716 FOUND 1/2" IRON (TIES MATCH PREVIOUS SURVEYS)

APPROVED

DATE 11-18-74

| | |
|--------|-------|
| MISC D | 9.00 |
| REMLC | P0075 |
| REMOVT | 2.00 |