

SURVEY & REMONUMENTATION

MAR 13 1998

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
97 NOV 12 PM 2:49

SECTION

For corners in: **MAYFIELD TWP.**

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>08N</u> R <u>10E</u>	<u>A-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; WAMPLER, D.S.; SET POST; ELM 7" S13W 80LKS., LINDEN 13" N35E 93LKS.
1977 HENDERSON-BATES; BATES, P.S.#16699; SURVEY; L.084,PG.408; SET IRON N10E 21.12' 10" BUTTERNUT, S50W 70.18' 12" OAK, S45E 47.16' 10" ASH
1978 HENDERSON-BATES; BATES, P.S.#16699; SURVEY; L.004,PG.474; FND. 1/2" ROD; SAME WITS AS 1977 SURVEY
1978 BATES, P.S.#16699; LCRC; L.003,PG.380; FND. 1/2" ROD; SAME WITS AS 1977 SURVEY ABOVE
1993 FIELD, P.S.#37276; 1993 REMON LCRC; FND. 1/2" ROD

A-13 TO A-12 2633.99' HENDERSON-BATES '77
A-13 TO M-12 2615.75' HENDERSON-BATES '77
A-13 TO L-13 2640.28' HENDERSON-BATES '77

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" W/ STANDARD REMON CAP

NOTE: THIS CORNER IS COMMON WITH A-13 T9N-R10E, M-13 T9N-R9E, AND M-1 T9N-R10E

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1 1/2" ROD W/ STANDARD REMON CAP
N13°E, 21.12' NAIL W/ REMON TAG IN NW FACE 10" ASH
S42°E, 47.16' NAIL W/ REMON TAG IN NE FACE 8" ASH
S70°W, 70.18' NAIL W/ REMON TAG IN N. FACE 16" OAK
N64°E, 33.53' NAIL W/ REMON TAG IN NW FACE 16" WILLOW
N60°W, 36.60' NAIL W/ REMON TAG IN SW FACE 8" ASH



Signed by Jonathan M. Field Date 11-11-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1971

LIGER 0005 PAGE 0447

SEER GROUP
APPROVED LAND CORNER
NOV 13 1997
MAYFIELD COUNTY
REGISTERED SURVEYOR
9-29-97

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

9