

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED RECORD

98 FEB 25 PM 3:10

For corners in
LAPEER

County	Located In:	Corner Code #
Public Land Survey	T 8N R 10E	A-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, MICHAEL G. HAY, in a field survey on AUGUST, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
NOT SET IN ORIGINAL SURVEY

- 1870 Gilbert Bates; stake; pine 30 S 88 W 6 Pine 40 southwest 34
- 1973 Bernard Henderson P.S. 16043 L002 P239 surveys fnd pipe N 30 E 64.55' 20" oak S 30 E 52.20 24" oak S 70 W 39.36 24" oak
- 1994 Harold N. Elrich P.S. 18986 L010 P694 surveys fnd iron pipe S 30 E 52.03 nail 28" oak N 30 W 25.96' nail 12" oak N 30 E 64.37 nail 30" oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 ROWE ENG: Michael G. Hay 41101 found 1/2" pipe on fence line heading North and fence heading east. Replaced with 1/2" iron and Remonumentation cap. Recovered 3 previous witnesses indication that found pipe is in the same position as 1973 sited above.

- A-4 to A-3 (no corner at A-3)
- A-4 to B-4 1970.13'
- A-4 to A-5 2658.70'
- A-4 to M-4 (Oregon) 91.71' SOUTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-4 replace 1/2" pipe with standard remon cap on 1/2" iron
- N 80 W 34.52' spike 13" oak
- N 30 W 25.96' spike 12" oak
- N 30 E 64.37' spike 30" oak
- S 30 E 52.03' spike 28" oak

Signed by Michael G. Hay Date September 26, 1997

Surveyor's Michigan License No. 41101