

**SURVEY &  
REMONUMENTATION**

MAR 13 1998

**SECTION**

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
98 FEB 26 PM 3:16

For corners in  
LAPEER

(County)

Located In:

Corner Code #

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>8N</u> R <u>10E</u> | <u>A-6</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

*Melvin DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MICHAEL G. HAY, in a field survey on AUGUST, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

NO CORNER SET ORIGINAL SURVEY

1874 Gilbert Bates C.S. stone 14 8 8 small stones earthen pine stump 27 S 76 W  
29 pine stump 27 N 57 E 11 1/4

1979 Bernard Henderson P.S. 16043 L005 P999 surveys S 55 W 34.67' 24" maple  
N 30 W 57.62' 8" tw cherry N 30 E 82.77' 8" cherry

1986 Harold N Elrich P.S. 18986 L007 P340 surveys.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Michael G. Hay PS # 41101 Found 1/2" iron in mon box in centerline of Millville Road and bush-tree line running to the East. Recover two witnesses close in recorded measured distance.

A-6 to A-5 2651.31' (m)

A-6 to A-7 2658.02' (m)

A-6 to M-6 90.95' (m) SOUTH

PEER GROUP  
APPROVED FOR CORNER

DATE 10-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Set standard remonumentation cap on found 1/2" iron in monument box

S45W - 37.62' - spike in 12" maple

N40W - 57.12' - p.k. nail and washer in 8"-6"-6"-4" cherry

N20E - 83.05' - p.k. nail and washer in 10" maple

S80E - 37.10' - spike in 6" maple



Signed by Michael G. Hay Date September 26, 1997

Surveyor's Michigan License No. 41101

EMER0006 PAGE 0028