

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

REMONUMENTATION RECEIVED FOR RECORD
LAND CORNER RECORDATION CERTIFICATE 98 FEB 26 PM 3:18
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>10E</u>	<u>A-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

William DeVaugh
 REGISTER OF DEEDS
 LAPEER, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MICHAEL G. HAY, in a field survey on AUGUST, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NO CORNER SET ORIGINAL SURVEY

1872 Gilbert Bates C.S., stake, pine stump 32 N 60 W 60 pine stump 34 S 54 W 89 pine 32 N 70 W 50

1981 Harold N. Elrich P.S. 18986 L006 P324 surveys fnd 1/2" iron

1982 Earl E. Gravlin P.S. 23510 L006 P506 surveys fnd 1/2" iron S 70 E 33.30' 12" maple S 25 W 57.25' utility pole N 50 W 46.84' 8" pine

1983 Earl E. Gravlin P.S. 23510 L006 P563 surveys fnd 1/2" iron S 70 E 32.30' 12" maple S 25 W 57.25 power pole N 50 W 46.94 8" pine

1987 Earl E. Gravlin P.S. 23510 L007 P831 surveys (same wits as 1982 survey above) 1990 Earl E. Gravlin P.S. 23510 L009 P102 Survey (same wits as 1982

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: above survey)

1997 Michael G. Hay PS # 41101 Found 1/2 " iron in mon box 1' West of centerline of Millville Road no occupation East-West. Recovered one witnesses from surveys. Iron is slightly twisted at the top.

A-8 to A-7 2662.80'

A-8 to A-9 2661.18'

A-8 to M-8 48.08' South

Michael G. Hay
 SURVEYOR
 DATE 10-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-8 Placed Remonumentation cap on 1/2" iron in Monument Box
- S 30 E 38.45' Nail and Remon washer in Telephone pole
- S 20 W 56.65' Nail and Remon washer in Power pole
- N 20 W 62.32' Nail and Remon washer in 8" pine
- S 60 E 33.01" Nail and Remon washer in 22" maple



Signed by Michael G. Hay

Date September 26, 1997

Surveyor's Michigan License No. 41101