

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 19 AM 11:21

LIBER NO. 05 DEED NO. 1665
Holmes & Naught 167
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

LAPEER
County

Located In:
MAYFIELD TWP

Corner Code ##

- | | | | | | |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>8N</u> | R | <u>10E</u> | <u>A-9</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH, in a field survey on NOV 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1824 SYLVESTER SIBLEY D.S. INTERSECTED 34 LINKS NORTH OF POST-SET POST AT INTERSECTION CORNER TO 19 & 30 WHITE OAK 30" S 22° E 68 LINKS, PINE 25" N 51° E 61 LINKS
 1974 HENDERSON P.S. LAND CORNER RECORDATION CERTIFICATE - LIBER 002, PAGE 559
 SET 1/2" IRON AT RECORDED DISTANCE OF 34 LINKS NORTH OF STANDARD CORNER FOUND AT S.E. COR. SECTION 24, T8N-R9E, N 20° E 61.04 FEET 18" CHERRY, N 45° E 54.47 FEET 24" OAK, S 85° E 30.97 FEET CORNER POST
 1980 HENDERSON P.S. LIBER 005, PAGE 686 - FOUND 1/2" IRON - N 20° E 62.04 FEET 18" CHERRY, N 45° E 54.47 FEET 24" OAK, S 85° E 30.97 FEET WOOD CORNER POST
 1982 GRAVLIN P.S. LIBER 006, PAGE 506 - FOUND 1/2" IRON - N 20° E 61.04 FEET 18" CHERRY S 85° E 30.97 FEET CORNER POST (OVER)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ELRICH P.S. FOUND 1/2" IRON ROD IN MONUMENT BDX, TWO FEET WEST OF CENTERLINE OF MILLVILLE ROAD. FENCE LINE RUNNING EAST OF IRON FOUND. FOUND THREE WITNESSES FROM PREVIOUS SURVEYS THAT VERIFY LOCATION OF 1/2" IRON. IRON FOUND IS NORTH 22.36 FEET FROM THE SOUTHWEST CORNER OF SECTION 24, T8N-R9E, OREGON TOWNSHIP. THE OLD NOTES INDICATE 34 LINKS (22.44 FEET) BETWEEN THESE CORNERS.

ACCEPTED 1/2" IRON FOUND AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHWEST CORNER OF SECTION 19, T8N-R10E, MAYFIELD TOWNSHIP, LAPEER COUNTY, MICHIGAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 PLACED REMONUMENTATION CAP ON 1/2" IRON ROD FOUND

NAIL & WASHER	18" CHERRY	N 20° E	61.08 FEET
NAIL & WASHER	24" OAK	N 45° E	54.45 FEET
NAIL & WASHER	TOP ANCHOR POST	S 85° E	30.68 FEET
NAIL & WASHER	8" ELM	S 45° E	58.37 FEET

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-19-94

Signed by Harold N. Elrich Date 12-9-94
 Surveyor's Michigan License No. 18986

A. (CONTINUED)

1983 HENDERSON P.S. LIBER 006, PAGE 516 SAME TIES AS 1980 SURVEY

1987 GRAVLIN P.S. LIBER 007, PAGE 831 SAME TIES AS 1980 SURVEY

1988 DAVIS P.S. LAPEER COUNTY RECORDATION CERTIFICATE LIBER 004,
PAGE 161 FOUND 1/2" IRON BAR AS RECORDED IN LIBER 002, PAGE
559 - S 45° W 81.85 FEET CHISELED "X" IN SIGN POST, EAST
30.70 FEET P.K. NAIL IN CORNER POST, N 15° E 61.00 FEET
P.K. NAIL IN 18" CHERRY, SOUTH 22.37 FEET SOUTHEAST CORNER
OF SECTION 24, T8N-R9E

1989 ELRICH P.S. LIBER 008 PAGE 638 FOUND 1/2" IRON IN MONUMENT
BOX (SAME TIES AS 1980 SURVEY) FOUND 1/2" IRON 22.36 FEET NORTH
OF SOUTHEAST CORNER OF SECTION 24, T8N-R9E, OREGON TOWNSHIP

1990 GRAVLIN P.S. LIBER 009, PAGE 102 FOUND 1/2" IRON (SAME TIES
AS 1980 SURVEY)

1992 GRAVLIN P.S. LIBER 009, PAGE 817 FOUND 1/2" IRON (SAME TIES
AS 1980 SURVEY)

1993 GRAVLIN P.S. LIBER 010, PAGE 425 FOUND 1/2" IRON IN MONUMENT
BOX (SAME TIES AS 1980 SURVEY)

1994 GRAVLIN P.S. LIBER 010, PAGE 577 FOUND 1/2" IRON IN MONUMENT
BOX (SAME TIES AS 1980 SURVEY)

MISC D	9.00
REMLC	P0075
REMONT	2.00