

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

98 FEB 26 PM 3:19

For corners in

<u>LAPEER</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>10E</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Melissa De Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MICHAEL G. HAY, in a field survey on AUGUST, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- 1867 Gilbert Bates, C.S.; Stake Brick - Willow 10 N 7 E 138, Pine 34 N 72 W 188
- 1980 Bernard Henderson PS # 16043 - L5, P686-687 - Set P.K. Nail - S20W 93.87' P.Pole, S40W 76.30 8" Oak, S30E 66.37' R.R. Tie Post, S25E 146.76' Wood Post, South 11.02' East 1/4 Cor. Sec. 25, T8N, R.E.
- 1989 Harold N. Enrich PS # 18986 - L., P638 - Found P.K. Nail - Same witnesses
- 1992 Earl E. Gravlin PS # 23510 - L9, P817 - Found P.K. Nail - Same witnesses
- 1993 Earl E. Gravlin PS # 23150 - L10, P142 - Found P.K. Nail - Same witnesses
- 1994 Earl E. Gravlin PS # 23510 - L10, P577 - Found Iron in Mon. Box - Same witnesses
- 1994 Earl E. Gravlin PS # 23510 - L10, P767 - Found 1/2" iron in Mon. Box - Same witnesses
- 1995 Earl E. Gravlin PS # 23510 = L11, P 283 - Found Iron in Mon Box - Same witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Michael G. Hay PS # 41101 Found 1/2" Iron in Mon. Box - Straight and in centerline of Millville Road. Recovered two of the previous witnesses indicating that found 1/2" iron in Mon Box is in the same position.


- A-10 to A-9 2661.76' (m)
- A-10 to A-11 2650.74' (m)
- A-10 to M-10 11.02'

APPROVED BY CORNER

Michael G. Hay
MICHIGAN STATE BOARD OF LAND SURVEYORS
DATE 10-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10 Set Standard Remonumentation cap on found 1/2" iron in Monument Box
- South - 11.02' - Remon. cap 1/2" iron in mon box
- S30E - 146.67' - Nail in Tel. Riser Pole
- S80E - 35.17' - Nail in top Fence Post
- S20W - 93.91' - Nail in P. Pole



Signed by Michael G. Hay Date September 26, 1997
Surveyor's Michigan License No. 41101