

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

94 DEC 19 AM 11:24

LIBER NO. 05 PAGE NO. 171

Melissa De Vaughn

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> <small>County</small>	Located In: <u>MAYFIELD TOWNSHIP</u>	Corner Code <u>##</u>
1. Public Land Survey	T <u>8N</u> R <u>10E</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, HAROLD N. ELRICH in a field survey on AUG 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1824 SYLVESTER SIBLEY D. S. A BEECH TREE 12" DIAMETER 1/4 SECTION CORNER
 - 1873 GILBERT EATES STAKE PINE 30" N 30° W 113 LINKS, PINE 36" S 10° W 144 LINKS
 - 1994 GRAVLIN P.S. FOUND 1/2 IRON IN MONUMENT BOX EAST 33.00 FEET FOUND IRON N 85° W 33.55 FEET 12" ELM, N 35° E 67.0 FEET 6" OAK
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994 ELRICH P.S. FOUND 1/2" IRON IN MONUMENT BOX, ONE FOOT EAST OF CENTERLINE OF FISH LAKE ROAD, EXISTING FENCE RUNNING EAST & WEST OF 1/2" IRON FOUND
 - FOUND 1/2" IRON MEASURED SOUTH 2673.20 FEET FROM 1/2" IRON IN MONUMENT BOX AND NORTH 2632.72 FEET FROM SOUTHWEST CORNER OF SECTION 24
 - DISTANCE FROM K-8 TO K-9 & THREE WITNESSES FROM 1994 SURVEY VERIFIED LOCATION OF THE 1/2" IRON FOUND IN MONUMENT BOX
 - ACCEPTED 1/2" IRON ROD AS BEST LOCATION OF ORIGINAL POSITION OF THE EAST 1/4 CORNER OF SECTION 23, T8N-R10E, MAYFIELD TOWNSHIP
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-8 PLACED REMONUMENTATION CAP ON 1/2" IRON ROD FOUND
 - NAIL & WASHER IN 12" ELM N 80° W 33.58 FEET
 - NAIL & WASHER IN TRIPLE OAK N 30° E 67.06 FEET
 - NAIL & WASHER IN 6" OAK N 80° E 36.83 FEET
 - NAIL & WASHER IN 5" ELM S 45° E 54.10 FEET

**PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY**

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 12-19-94

Signed by Harold N. Elrich Date 12-9-94
Surveyor's Michigan License No. 18985