

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:43

LIBER NO. 05 PAGE NO. 100
Nelson D. Elrich
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in <u>LAPEER</u> <small>County</small>	Located In: <u>MAYFIELD TOWNSHIP</u>	Corner Code ## <u>K-9</u>
1. Public Land Survey	T <u>8N</u> R <u>10E</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on AUG 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1824 SYLVESTER SIBLEY D.S. SET POST COMMON TO SECTIONS 23,24, 25 & 26 IN SWAMP, BIRCH 4"
 S 68° E 7 LINKS, WHITE OAK 5" S 7½° W 24 LINKS
 1873 GILBERT BATES STAKE - WHITE OAK 28" N 80° W 115 LINKS, PINE 16" S 68" W 125 LINKS
 1973 KAY P.S. LIBER 002, PAGE 199 NO OBJECT STATED N 50° W 48.06 FEET NAIL IN POWER POLE,
 N 45° E 45.05 FEET NAIL IN POWER POLE, S 40° E 45.6 FEET NAIL IN POWER POLE
 1973 KAY P.S. LIBER 002, PAGE 214 NO OBJECT STATED (TIES SAME AS PREVIOUS SURVEY)
 1982 ELRICH P.S. LIBER 004, PAGE 047 - FOUND RAILROAD SPIKE IN MONUMENT BOX (NO TIES)
 1990 ELRICH P.S. LIBER 008, PAGE 692 - FOUND RAILROAD SPIKE IN MONUMENT BOX, S 45° E
 48.45 FEET POWER POLE, N 45° E 44.34 FEET POWER POLE, N 45° W 60.24 FEET ANCHOR POLE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 ELRICH P.S. FOUND RAILROAD SPIKE IN MONUMENT BOX AT THE INTERSECTION OF THE
 CENTERLINE OF DALEY ROAD AND THE CENTERLINE OF FISH LAKE ROAD. FOUND THREE
 WITNESSES FROM PREVIOUS SURVEYS THAT VERIFY THE LOCATION OF THE RAILROAD
 SPIKE FOUND

ACCEPTED THE FOUND RAILROAD SPIKE AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHWEST
 CORNER OF SECTION 24, T8N-R10E, MAYFIELD TOWNSHIP

HAROLD N. ELRICH
 REGISTER OF DEEDS
 LAPEER COUNTY, MICHIGAN
 DATE 11-13-94

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-9 REMOVED RAILROAD SPIKE AND SET 1/2" IRON ROD WITH STANDARD
 REMONUMENTATION CAP

- NAIL & WASHER IN POWER POLE S 45° E 48.45 FEET
- NAIL & WASHER IN POWER POLE N 45° E 44.34 FEET
- NAIL & WASHER IN ANCHOR POLE N 45° W 60.24 FEET
- NAIL & WAHSER IN POWER POLE S 80° W 284.98 FEET



Signed by Harold N. Elrich Date NOV 3, 1994
 Surveyor's Michigan License No. 18986