

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 NOV 18 PM 1:45

LIBER NO. 65 PAGE NO. 101 -
Harold N. Elrich
102
REGISTERED PROFESSIONAL
LAND SURVEYOR JAN 21 1983

For corners in			
<u>LAPEER</u>	Located In:	Corner Code #	
County	MAYFIELD TOWNSHIP		
1. Public Land Survey	T <u>8N</u> R <u>10E</u>	<u>M-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, HAROLD N. ELRICH in a field survey on AUG 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1824 SYLVESTER SIBLEY D.S. SET POST COMMON WITH SECTIONS 24 & 25
SUGAR 12" N 20° W 54 LINKS, SUGAR 14" N 72° W 25 LINKS
1872 GILBERT BATES STAKE - APPLE 2" S 42½° W 56 LINKS, PINE STUMP 38" S 12½° E 204 LINKS
1976 ELRICH P.S. LIBER 003, PAGE 242 LAND CORNER RECORDATION CERTIFICATE-FOUND RAILROAD SPIKE, REPLACED WITH 1/2" IRON ROD - N 10° E 125.02 FEET POWER POLE, S 80° W 101.54 FEET 30" OAK, N 10° W 103.67 FEET POWER POLE
1976 ELRICH P.S. LIBER 003, PAGE 811-1/2" IRON (SAME TIES AS 1976 LAND CORNER RECORDATION CERTIFICATE)
(SEE BACK)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ELRICH P.S. FOUND 1/2" IRON IN CENTERLINE OF FIVE LAKES ROAD AND PROJECTION OF DALEY ROAD CENTERLINE FROM THE WEST. FOUND ONE WITNESS THAT CHECKED FROM PREVIOUS SURVEYS. ALSO CHECKED THE DISTANCE FROM SOUTHWEST CORNER OF SECTION 19, T8N-R11E, ARCADIA TOWNSHIP FROM PREVIOUS SURVEY. THE DISTANCE BETWEEN CORNERS IS 59.13 FEET. THE ORIGINAL SURVEY INDICATED 106 LINKS (69.96 FEET)

ACCEPTED FOUND 1/2" IRON ROD AS BEST LOCATION OF ORIGINAL POSITION OF SOUTHEAST CORNER OF SECTION 24, T8N-R10E, MAYFIELD TOWNSHIP

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9 SET REMONUMENTATION CAP OVER FOUND 1/2" IRON ROD

- NAIL & WASHER IN 32" OAK S 80° W 101.54 FEET
- NAIL & WASHER IN POWER POLE N 25° W 66.01 FEET
- NAIL & WASHER IN TRIPLE OAK (6", 8" 10") N 10° E 161.37 FEET
- NAIL & WASHER IN 14" HICKORY S 10° W 135.84 FEET

Signed by Harold N. Elrich Date Nov 3, 1994
Surveyor's Michigan License No. 18986



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN 1982

A. (CONTINUED)

1978 ELRICH P.S. LIBER 004, PAGE 854 FOUND 1/2" IRON (SAME TIES AS 1976 LAND CORNER RECORDATION CERTIFICATE)

1980 BATES P.S. LIBER 005, PAGE 937 NO OBJECT STATED (SAME TIES AS 1976 LAND CORNER RECORDATION CERTIFICATE)

1984 GRAVLIN P.S. LIBER 006, PAGE 753 NO OBJECT STATE (SAME TIES AS 1976 LAND CORNER RECORDATION CERTIFICATE)

1993 ELRICH P.S. LIBER 010, PAGE 338 NO OBJECT STATED CORNER SHOWN IS 59.6 FEET SOUTH OF SOUTHWEST CORNER OF SECTION 19, T8N-R11E, ARCADIA TOWNSHIP,

APPROVED
RAY C. [Signature]
DATE 11-13-94

MISC D	9.00
REMLC	F0075
REMOVT	2.00