

SURVEY & REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 2:57

LIBER NO. 5 PAGE NO. 26

Harold N. Elrich
LAND SURVEYOR
LAPEER

For corners in

LAPEER

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>8N</u> R <u>10E</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH in a field survey on NOVEMBER, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GLO SURVEY BY JOS. WAMPLER D.S. SET POST
IRONWOOD 10" NORTH 4 1/2° WEST 52 LINKS & BEECH 11" SOUTH 86° WEST 35 LINKS
1872 GILBERT BATES SET STONE 16" X 10" X 4" AND BRICK
SWAMP OAK 10" SOUTH 15° EAST 211 LINKS, SUGAR 14" SOUTH 8°10' WEST 167 LINKS
1980 RECORDED SURVEY LIBER 005, PAGE 969 FOUND 1/2" IRON ROD HENDERSON P.S. #16043

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1973 NOV. ELRICH P.S. #18986 FOUND 1/2" IRON ROD ON CENTERLINE OF FIVE LAKES, 15 FEET SOUTH OF CENTERLINE OF HAINES ROAD
THREE WITNESS TIES MATCHED THE 1980 SURVEY AND THE DISTANCE FROM THE SOUTHWEST CORNER OF SECTION 30, ARCADIA TOWNSHIP, TO THE NORTHEAST CORNER OF SECTION 36, CHECKED THE DISTANCE OF 24.9 FEET RECORDED ON THE SURVEY

ACCEPTED THE IRON ROD FOUND AS BEST EVIDENCE OF ORIGINAL POSITION OF THE NORTHEAST CORNER OF SECTION 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 1/2" IRON ROD WITH REMONUMENTATION CAP
24.95 FEET NORTH TO IRON ROD USED AS SOUTHWEST CORNER OF SECTION 30
NORTH 45° EAST 58.97 FEET NAIL & REMONUMENTATION TAG IN POWER POLE
SOUTH 45° EAST 43.61 FEET NAIL & REMONUMENTATION TAG IN POWER POLE
SOUTH 65° EAST 73.25 FEET NAIL & REMONUMENTATION TAG IN POWER POLE
NORTH 75° EAST 232.74 FEET NAIL & REMONUMENTATION TAG IN POWER POLE

Signed by *Harold N. Elrich*

Date 12-1-93

Surveyor's Michigan License No. 18986



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
RECEIVED JAN., 1983