

SURVEY &  
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 22 PM 2:59

LIBER NO. 5 FILE NO. 28  
LAPPEER  
REGISTER OF DEEDS

For corners in

LAPPEER  
(County)

Located In:

Corner Code #

- |                                    |   |           |   |            |             |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey              | T | <u>8N</u> | R | <u>10E</u> | <u>M-13</u> |
|                                    | T |           | R |            |             |
|                                    | T |           | R |            |             |
|                                    | T |           | R |            |             |
| 2. Property Controlling in Section | S |           | T | R          |             |
|                                    | S |           | T | R          |             |
| 3. Miscellaneous Property in Sec.  | S |           | T | R          |             |
|                                    | S |           | T | R          |             |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, HAROLD N. ELRICH, in a field survey on NOVEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL GLO SURVEY BY JOS. WAMPLER D.S. SET POST  
ASPIN 9" NORTH 55 1/2° WEST 34 LINKS & ASPIN 8" NORTH 50 1/2° EAST 51 LINKS  
1872 GILBERT BATES SET 4 FOOT LONG WHITE OAK STAKE, STONE & BRICK ON WEST SIDE CINDERS  
SOUTHEAST CORNER OF HOTEL NORTH 41° WEST 48 LINKS  
1980 RECORDED SURVEY LIBER 005, PAGE 812 FOUND 3/4" IRON ROD IN MONUMENT BOX GRAVLIN #23510  
1986 RECORDED SURVEY LIBER 007, PAGE 158 FOUND 3/4" IRON ROD GRAVLIN P.S.#23510  
1989 LAND CORNER RECORDATION CERTIFICATE LIBER 004, PAGE 249 GRAVLIN P.S. #23510

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 NOV ELRICH P.S. #18986 FOUND 3/4" IRON ROD IN MONUMENT BOX AT CENTERLINE OF FIVE LAKES & BOWERS ROAD

TWO WITNESSES MATCHED RECORDED SURVEYS IN 1980 AND 1986 AND THE 1989 LAND CORNER RECORDATION CERTIFICATE

ACCEPTED THE IRON ROD AS BEST EVIDENCE OF ORIGINAL POSITION OF SOUTHEAST CORNER OF SECTION 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 3/4" IRON ROD WITH REMONUMENTATION CAP IN MONUMENT BOX  
NORTH 45° WEST 51.46 FEET NAIL & REMONUMENTATION TAG IN POWER POLE  
SOUTH 35° WEST 73.00 FEET NAIL & REMONUMENTATION TAG IN TELEPHONE POLE  
SOUTH 30° EAST 72.60 FEET NAIL & REMONUMENTATION TAG IN TELEPHONE POLE  
NORTH 40° EAST 49.34 FEET NAIL & REMONUMENTATION TAG IN POWER POLE

Signed by Harold N. Elrich Date 12-1-93  
Surveyor's Michigan License No. 18986

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

