

**SURVEY &
REMONUMENTATION**

APR 29 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in

Lapeer
(County)

Located In:
ARCADIA TOWNSHIP

Corner Code #

- | | | | | | |
|---|---|-----------|---|------------|------------|
| 1. Public Land Survey | T | <u>8N</u> | R | <u>11E</u> | <u>M-4</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous
Property in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

95 DEC 28 PM 2:42

LIBER NO. 005 PAGE NO. 329

Malissa DeLong
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, James T. Bailey, in a field survey on December 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (1822) WAMPLER D.S. SET POST NO WITNESSES FOUND
- L.C.R.C. GRAVLIN P.S. L.4 P.170 FOUND 1/2" IRON
- SURVEY KAY P.S. L.4 P.173 FOUND 1/2" IRON
- SURVEY GRAVLIN P.S. L.7 P.439 FOUND 1/2" IRON
- SURVEY GRAVLIN P.S. L.7 P.859 FOUND 1/2" IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 JAMES T. BAILEY P.S. FOUND 1/2" IRON 2" BELOW GRADE AT THE CENTERLINE OF SUMMERS ROAD (GRAVEL) AND EWALT ROAD (GRAVEL). WITNESSES FROM ITEMS #2 AND 5 ABOVE MATCH.

DISTANCE TO M-5 2666.33


PEEP GROUP
APPROVED LAND CORNER
PA 345 OF 1980
LAPEER COUNTY

Ray Davis
RAY DAVIS P.S. CO. SURVEYOR
DATE 7-13-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 SET STANDARD LAPEER COUNTY REMONUMENTATION CAP ON FOUND 1/2" IRON

- N.20°E. 136.71 SET PK NAIL W/ REMON TAG IN W'LY SIGN POST
- S.40°W. 69.52 SET PK NAIL W/ REMON TAG IN 14" OAK
- S.75°W. 71.01 SET PK NAIL W/ REMON TAG IN 10" OAK
- N.30°W. 100.89 SET PK NAIL W/ REMON TAG IN 10" MAPLE



Signed by *JT Bailey*

Date DECEMBER 19, 1995

Surveyor's Michigan License No. 33968

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1963