

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> <small>(County)</small>	Located In: ARCADIA TOWNSHIP	Corner Code #: M-6
1. Public Land Survey	T <u>8N</u> R <u>11E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

95 JAN -3 PM 3:52

LIBER NO. 05 PAGE NO. 207

Melissa D. Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JAMES T. BAILEY, in a field survey on OCTOBER 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. G.L.O. (1822) JOSEPH WAMPLER SET POST, 5" BEECH N.67½°W. 19LKS, 5" TREE S.56½°W. 20 LKS.
 2. LCRC (1978) GRAVLIN P.S. LIBER 003, PAGE 552, SET ½" IRON, 3 WITNESSES GIVEN
 3. SURVEY (1978) GRAVLIN P.S. LIBER 004, PAGE 943, SET ½" IRON, 3 WITNESSES GIVEN
 4. SURVEY (1986) GETZ P.S. LIBER 007, PAGE 493, FD. ½" IRON, 4 WITNESSES GIVEN
 5. SURVEY (1987) GETZ P.S. UNRECORDED, FD. ½" IRON, 4 WITNESSES GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 JAMES T. BAILEY P.S. FOUND ½" IRON ROD 2' WEST OF THE CENTERLINE OF SUMMERS ROAD, AT GRADE. FOUND COMMON WITNESSES FROM ITEMS 2 - 5 FROM ABOVE.


ACCEPTED ½" IRON ROD AS BEST LOCATION OF ORIGINAL POSITION OF THE EAST ¼ CORNER OF SECTION 13, T8N-R11E, ARCADIA TOWNSHIP.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS, S. CO. SURVEYOR
DATE 1-3-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-6 SET STANDARD REMONUMENTATION CAP ON FOUND ½" IRON ROD.

- N.45°E. 36.94 SET NAIL W/ REMON TAG IN N.W. FACE 34" MAPLE
- N.07°E. 26.03 SET NAIL W/ REMON TAG IN SOUGH FACE 18" MAPLE
- S.20°E. 27.01 SET NAIL W/ REMON TAG IN S.W. FACE 24" MAPLE
- S.40°E. 36.74 SET NAIL W/ REMON TAG IN S.W. FACE 20" MAPLE
- S.20°E. 26.96 FD. 16 "D" NAIL IN S.W. FACE 24" MAPLE
- N.10°E. 25.77 FD. 16 "D" NAIL IN NORTH FACE 18" MAPLE
- N.45°E. 36.95 FD. 16 "D" NAIL IN N.W. FACE 34" MAPLE



Signed by *James T. Bailey* Date DECEMBER 29, 1994
Surveyor's Michigan License No. 33968