

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>LAPEER</u> County	Located In: ARCADIA TOWNSHIP	Corner Code #: M-7
1. Public Land Survey	T <u>8N</u> R <u>11E</u>	M-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

95 JAN -3 PM 3:55

LIBER NO. 05 PAGE NO. 209

Helen De Vangh

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JAMES T. BAILEY, in a field survey on OCTOBER 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. (1822) JOSEPH WAMPLER SET POST, 7" ASH N.62°W. 19 LKS, 6" BEECH S.57°W. 24 LKS
- LCRC (1991) GRAVLIN P.S. LIBER 004, PAGE 378, FD. IRON, 3 WITS GIVEN
- SURVEY (1978) GRAVLIN P.S. LIBER 004, PAGE 943, NO OBJECT STATED, 3 WITS GIVEN
- SURVEY (1994) GRAVLIN P.S. LIBER 010, PAGE 373, FD. 1/2" IRON, 3 WITS GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 JAMES T. BAILEY P.S. FOUND 1/2" IRON 4" BELOW GRADE AT THE CENTERLINE OF SUMMERS ROAD AND THE CENTERLINE OF LYONS ROAD TO THE EAST. FOUND 1 COMMON WITNESS FROM ITEMS 2 & 3 FROM ABOVE. FOUND 3 COMMON WITNESSES FROM ITEM 4 FROM ABOVE.

ACCEPTED 1/2" IRON AS BEST LOCATION OF ORIGINAL POSITION OF THE SOUTHEAST CORNER OF SECTION 13, T8N-R11E, ARCADIA TOWNSHIP.


APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY

Ray Davis
RAY DAVIS, P.E., CO. SURVEYOR
DATE 1-3-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 SET STANDARD REMONUMENTATION CAP ON FOUND 1/2" IRON.

NORTH 89.45 FD. 1/2" IRON 4" BELOW GRADE @ Q SUMMERS RD. & Q LYONS RD TO THE EAST
N.40°W. 56.23 SET NAIL W/ REMON TAG IN S.W. FACE T.P.
S.65°W. 80.88 SET NAIL W/ REMON TAG IN NORTH FACE 12" MAPLE
S.12°W. 153.33 SET NAIL W/ REMON TAG IN EAST FACE P.P.
N.40°W. 55.99 FD. P.K. NAIL IN EAST FACE T.P.
S.65°W. 81.12 FD. 16 "D" NAIL IN NORTH FACE 12" MAPLE



Signed by James T. Bailey Date DECEMBER 29, 1994
Surveyor's Michigan License No. 33958