

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LAPEER
County

Located In: ARCADIA TOWNSHIP Corner Code M-8

1. Public Land Survey	T	<u>8N</u>	R	<u>11E</u>	<u>M-8</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD

95 JAN -3 PM 3:54

LIBER NO. 65 PAGE NO. 208

Melissa De Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	15	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES T. BAILEY, in a field survey on OCTOBER 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. (1822) JOSEPH WAMPLER SET POST, 9" TREE S.52°W. 8 LKS, 9" TREE N.23½°W. 29 LKS.
 - LCRC (1972) ELRICH P.S. LIBER 001, PAGE 499, FD. R/R SPIKE, 3 WITS GIVEN
 - LCRC (1976) BECK P.S. LIBER 003, PAGE 222, FD. R/R SPIKE, 3 WITS GIVEN
 - SURVEY (1976) BECK P.S. LIBER 003, PAGE 680, FD. R/R SPIKE
 - SURVEY (1977) ELRICH P.S. LIBER 004, PAGE 387, FD. R/R SPIKE
 - SURVEY (1978) GETZ P.S. LIBER 005, PAGE 218, FD. R/R SPIKE
 - SURVEY (1994) GRAVIN P.S. LIBER 010, PAGE 373, FD. R/R SPIKE
 - SURVEY (1988) BROWN P.S. UNRECORDED, FD. R/R SPIKE
 - SURVEY (1992) BAILEY P.S. UNRECORDED, FD. R/R SPIKE
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 JAMES T. BAILEY P.S. FOUND R/R SPIKE AT GRADE IN THE CENTERLINE OF ~~SUMMERS ROAD (ASPHALT)~~ AND LUM ROAD (ASPHALT). FOUND 2 WITNESSES COMMON FROM ITEMS 2 & 3 FROM ABOVE. FOUND NUMEROUS COMMON TO ABOVE LISTED SURVEYS.

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1000
LAPEER COUNTY

RAY DAVIS P.S. CO. SURVEY


DATE 1-3-95

M-8 TO L-8 MEAS. 2637.16
M-8 TO M-9 MEAS. 2644.29

ACCEPTED R/R SPIKE AS BEST LOCATION OF ORIGINAL POSITION OF THE EAST ¼ CORNER OF SECTION 24, T8N-R11E, ARCADIA TOWNSHIP.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 SET ½" ROD WITH STANDARD REMONUMENTATION CAP IN MONUMENT BOX.

S.30°W. 117.98 SET NAIL W/ REMON TAG IN S.W. FACE T.P.
N.05°E. 27.27 SET NAIL W/ REMON TAG IN SOUTH FACE 8" LOCUST
N.35°E. 77.37 SET NAIL W/ REMON TAG IN N.W. FACE T.P.
N.45°W. 75.73 SET NAIL W/ REMON TAG IN S.W. FACE T.P.
N.35°E. 77.35 FD. NAIL IN N.W. FACE T.P.



Signed by James T. Bailey
Surveyor's Michigan License No. 33968

Date DECEMBER 29, 1994