

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____
LAPEER Located In: _____ Corner Code ##
(County) ARCADIA TOWNSHIP

1. Public Land Survey	T <u>8N</u> R <u>11E</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD
 95 JAN -3 PM 3:56
 LIBER NO. 05 PAGE NO. 210
Melissa DeVaugh
 REGISTER OF DEEDS
 LAPEER COUNTY, MICHIGAN
 Register of Deeds Stamp & File Number

I, JAMES T. BAILEY in a field survey on OCTOBER 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. G.L.O. (1822) JOSEPH WAMPLER SET POST, 16" BEECH S.89°W. 29 LKS, 16" TREE N.19½°W. 39'
 2. LCRC (1991) GRAVLIN P.S. LIBER 004, PAGE 367, FD. ½" IRON, 3 WITS GIVEN
 3. SURVEY (1986) GRAVLIN P.S. LIBER 007, PAGE 312, FD. IRON, 3 WITS GIVEN
 4. SURVEY (1990) GRAVLIN P.S. LIBER 009, PAGE 073, FD. ½" IRON, 3 WITS GIVEN
 5. SURVEY (1992) BAILEY P.S. UNRECORDED, FD. ½" IRON, 4 WITS GIVEN


- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 JAMES T. BAILEY P.S. FOUND ½" IRON ROD IN CENTERLINE OF SUMMERS ROAD (ASPHALT) ON THE EXTENSION OF A FENCE LINE TO THE WEST. WITNESSES TO ITEM 2 GONE. WITNESS NORTH 68.22 TO NORTHWEST CORNER, SEC. 30, T8N-R12E, IS COMMON TO ITEMS 3 & 4 FROM ABOVE.

ACCEPTED ½" IRON AS BEST LOCATION OF ORIGINAL POSITION OF THE SOUTHEAST CORNER OF SECTION 24, T8N-R11E, ARCADIA TOWNSHIP.

PEER GROUP
 APPROVED LAND CORNER
 PA 345 OF 1990
 LAPEER COUNTY
James T. Bailey
 JAMES T. BAILEY P.S. CO. SU.
 DATE 1-3-95

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-9 SET ½" IRON ROD WITH STANDARD REMONUMENTATION CAP IN MONUMENT BOX.

- N.85°W. 33.55 SET NAIL W/ REMON TAG IN SOUTH FACE 36" MAPLE
- N.85°E. 35.49 SET NAIL W/ REMON TAG IN NORTH FACE 21" MAPLE
- S.75°E. 39.64 SET NAIL W/ REMON TAG IN SOUTH FACE 8" ASH
- S.30°E. 78.60 SET NAIL W/ REMON TAG IN WEST FACE OF GUY POLE
- N.85°W. 33.56 FD. NAIL IN SOUTH FACE 36" MAPLE
- S.30°E. 78.60 FD. P.K. NAIL IN WEST FACE OF GUY POLE



Signed by James T. Bailey Date DECEMBER 29, 1994
 Surveyor's Michigan License No. 33968