

SURVEY &
REMONUMENTATION

1993

COMMISSION

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LAPEER
(County)

Located In:
Arcadia

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>8N</u> R <u>11E</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD

94 JAN -5 PM 1:23

LIBER # 005 PAGE NO. 73
Melissa Miles
REGISTERED DEEDS
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

I, John C. Niederhauser in a field survey on Nov. 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Temp. Post (G.L.O. Notes, pg. 412)

Beech 14" N 63W 8'
D Oak 6" S 60W 29'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1/2" rerod

2639.12' South to E 1/4 corner Section 36
2636.56' North to E 1/4 corner Section 25

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set brass disk stamped "Lapeer County Remonumentation M-11 #24608"
North to 1/2" rerod (SW Corner Section 30) 75.24'
SW to nail w/remon. tag E side 28" oak 42.88'
W to nail w/remon. tag S side guy pole 31.14'
NE to nail to nail w/remon. tag S side guy pole 55.88'



Signed by [Signature] Date Dec. 30, 1993

Surveyor's Michigan License No. 24608