

**SURVEY &  
REMONUMENTATION**

**MAR 23 2000**

**SECTION**

**REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
GOODLAND TOWNSHIP**

For corners in

<u>LAPEER</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>8</u> N R <u>12</u> E	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD

00 JAN 19 AM 8:48

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

463

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, SHELBY W. MONEY, in a field survey on September 25, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more that 4 comers, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Not set by the GLO  
1. L4, Pg 452, November 1977 survey by Henderson Bates, Found 1/2" iron. A-2, T8N, R12E  
2. L6, Pg 862 August 1984 survey by survey by Henderson Bates. A-1, T8N, R12E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" rerod in Summers Road (gravel) at the intersection with Stine Road. The corner is 3' west of the physical centerline of Summers road and 3.5' south of th ephysical centerline of Stine road, 0.3' below the surface.

Witness found: None

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" rerod stamped #30092 as the best location for this corner as accepted by the Professional Surveyors in this area.

- AZ 25° 47.91' Set mag nail with Lapeer remon tag in northwest face 13" Maple.  
AZ 65° 44.82' Found nail in west face of fence post.  
AZ 110° 77.15' Set mag nail with Lapeer remon tag in north face 12" Cherry.  
AZ 230° 152.40' Set mag nail with Lapeer remon tag in face triple 18" poplar.  
AZ 320° 33.68' Found nail with Rowe witness tag in northeast face utility pole.  
South 54.03' M-2, T8N, R11E  
North 2739.45 to A-1  
South 2669.63 to A-3



Signed by *Shelby W. Money* Date 12/29, 1999

Surveyor's Michigan License No. 30092

PEER GROUP  
APPROVED LAND CORNER

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISD MAY 14, 1975  
REVISED JAN., 1983

*Ray Davis*  
RAY DAVIS P.S. CO. SURVEYOR  
DATE 11-10-99

LIBER 0006 PAGE 0256