

SURVEY &
REMONUMENTATION

MAR 23 2000

SECTION

REMONUMENTATION

RECEIVED FOR RECORD

00 JAN 19 AM 8:48

Melissa DeVough
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
GOODLAND TOWNSHIP

For corners in

LAPEER Located In: Corner Code #
(County)

- | | | | |
|------------------------------------|--------------|---------------|------------|
| 1. Public Land Survey | T <u>8</u> N | R <u>12</u> E | <u>A-3</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

464

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on September 25, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER

REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

11-10-99

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Post set by Wampler in 1822 206 lns north of M-3 T8N, R11E.

- L4, Pg 183, December 1988 LCRC by Earl Gravlin, Found iron, A-3, T8N, R12E
- L4, Pg 896, September 1978 survey by James A. Beck, Not identified, A-3, T8N, R12E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" rerod in Summers Road (gravel). The corner is in the physical centerline of Summers road 6" below the surface.

Witness found: From items 1 and 2,
S 55°W 33.20' Nail in 10" Cherry.
S 45° E 74.88' Nail in power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" rerod stamped #30092 as the best location for this corner as accepted by the Professional Surveyors in this area.

- AZ 35° 53.60' Set mag nail with Lapeer remon tag in northwest face triple 8" Cedar.
- AZ 95° 32.97' Found 1/2" rerod.
- AZ 140° 75.00' Found nail in southwest face of power pole.
- AZ 230° 33.18' Found nail in northeast face of 13" Cherry.
- AZ 260° 21.72' Set mag nail with Lapeer remon tag in north face twin 8" Birch, below found nail.
- AZ 350° 78.61' Set mag nail with Lapeer remon tag in east face 13" Aspen.
- South 144.66' to M-3, T8N, R11E
- North 2669.63 to A-2
- South 2645.73 to A-4

Signed by SHELBY W. MONEY
Surveyor's Michigan License No. 30092



Date 12/29, 1999