

SURVEY &
REMONUMENTATION

MAR 23 2000

SECTION

RECEIVED FOR RECORD

00 JAN 19 AM 8:49

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
GOODLAND TOWNSHIP

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

For corners in

LAPEER (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> N R <u>12</u> E	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

465

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, SHELBY W. MONEY, in a field survey on September 25, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Not set by the GLO

- L1, Pg 117, September 1971 survey by Kay Engineering, Found 3/8" iron. A-4, T8N, R12E
- L1, Pg 426, May 1972 survey by Kay Engineering, not identified. A-4, T8N, R12E
- L4, Pg 183, December 1988 LCRC by Earl Gravin, Found iron. A-4, T8N, R12E
- L4, Pg 896, September 1978 survey by James Beck, not identified. A-4, T8N, R12E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" rebar in Summers Road (gravel) road. The corner is 1' west of the physical centerline 2" below surface. The following witnesses from the recorded documents were used to locate the corner:

Witness found: From item 1
N 75°W 28.9' Nail in 8" Maple.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4 We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" rebar stamped #30092 as the best location for this corner as accepted by the Professional Surveyors in this area.

- AZ 45° 47.91' Found nail with Lapeer County remon. tag in West face of West sign post (Camp Michael).
- AZ 85° 113.28' Set mag nail with Lapeer County remon tag in South face of twin 11" & 7" Oak.
- AZ 100° 122.66' Set mag nail with Lapeer County remon. tag in North face of 11" Poplar.
- AZ 195° 157.40' Found PK nail with Lapeer County remon. tag in Northwest face of 20" Basswood.
- AZ 305° 28.67' Set mag nail with Lapeer County remon. tag in South face of multi 10" Maple.
- South 97.64' to M-4, T8N, R11E.
- North 2645.73 to A-3
- South 2659.44 to A-5

Signed by *Shelby W. Money*
Surveyor's Michigan License No. 30092



12/29/99

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 21 1971
REVISED MAY 14, 1971
REVISED JAN., 1981