

**SURVEY &  
REMONUMENTATION**

**MAR 23 2000**

**SECTION**

**REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
GOODLAND TOWNSHIP**

For corners in

|                                       |                            |               |
|---------------------------------------|----------------------------|---------------|
| <u>LAPEER</u><br>(County)             | Located In:                | Corner Code # |
| 1. Public Land Survey                 | T <u>8 N</u> R <u>12 E</u> | <u>A-5</u>    |
|                                       | T _____ R _____            | _____         |
|                                       | T _____ R _____            | _____         |
|                                       | T _____ R _____            | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____    | _____         |
|                                       | S _____ T _____ R _____    | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____    | _____         |
|                                       | S _____ T _____ R _____    | _____         |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, **SHELBY W. MONEY**, in a field survey on September 25, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Post set by Wampler in 1822 165 Inks north of M-5 T8N, R11E.
- L1, Pg 117, September 1971 survey by Kay Engineering, Found 3/8" iron. A-5, T8N, R12E
  - L1, Pg 426, May 1972 survey by Kay Engineering, not identified. A-5, T8N, R12E
  - L3, Pg 99, June 1975 LCRC by Bernard Henderson, Found 1/2" iron rod. A-5, T8N, R12E
  - L3, Pg 392, June 1975 survey by Bernard Henderson, Found 1/2" iron rod. A-5, T8N, R12E
  - L3, Pg 444, September 1975 survey by Bernard Henderson, Found 1/2" iron rod. A-5, T8N, R12E
  - L6, Pg 1000, May 1985 survey by Earl Gravlin, Found 1/2" iron rod. A-5, T8N, R12E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found a 1/2" rered in Summers Road (gravel) road. The corner is in physical centerline of road 2" below surface. There is a tree row to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 We placed a standard Lapeer County Remonumentation Brass cap on the found 1/2" rebar stamped #30092 as the best location for this corner as accepted by the Professional Surveyors in this area.

- AZ 95° 56.01' Found PK nail in the North face of a utility pole.
  - AZ 170° 133.29' Set mag nail with Lapeer County remon tag in Southwest face twin 6" box elder.
  - AZ 205° 48.15' Found PK nail with Lapeer County remon tag in Northeast face quad 12" box elder.
  - AZ 270° 25.56' Set mag nail with Lapeer County remon. tag in South face 20" box elder.
  - AZ 355° 114.15' Set mag nail with Lapeer remon. tag in East face 13" box elder.
- South 104.42' M-5 T8N, R11E  
North 2659.44 to A-4  
South 2659.60 to A-6

Signed by *Shelby W. Money*  
Surveyor's Michigan License No. 30092



Date 12/29/99

RECEIVED FOR RECORD  
00 JAN 19 AM 8:49

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

*Hele*

**Register of Deeds Stamp & File Number**

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

DEED GROUP  
APPROVED FOR RECORD

*Shelby W. Money*  
DATE 11-10-99