

**SURVEY & REMONUMENTATION**

**MAR 23 2000**

RECEIVED FOR RECORD

00 JAN 19 AM 8:49

**REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
GOODLAND TOWNSHIP**

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

For corners in

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> N R <u>12</u> E	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

470

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, SHELBY W. MONEY, in a field survey on September 25, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 comers, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- Township line surveyed in 1816 by Wampler for T8N, R11E Arcadia Twp.  
GLO Post set by Wampler in 1822 111 Lnks north of M-9 T8N, R11E
- L1, Pg 255, November 1971, survey by Bernard Henderson, Not identified, A-9, T8N, R12E
  - L3, Pg 778, September 1976 survey by James A. Beck, Found nail, A-9, T8N, R12E
  - L4, Pg 366, May 1991, LCRC, Earl E. Gravlin, Found nail, A-9, T8N, R12E
  - L8, Pg 963, June 1990, survey by Earl A. Gravlin, Found nail, A-9, T8N, R12E

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found a nail in the centerline of Summers Road (asphalt) at the Intersection with Armstrong Road to the east (asphalt).

Witness found:

- Az 150° 60.2' to centerline of stump at ground surface.
- AZ 215° 70.55' set mag nail with Lapeer remon tag in East face of 34" Maple, below found nail.
- AZ 340° 73.20' found double head nail in East of 48" Maple.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8 We placed a standard Lapeer County Remonumentation Brass cap on a rod at the corner stamped #30092 as the best location for this corner as accepted by the Professional Surveyors in this area.

- AZ 45° 50.20' to mag nail with Lapeer remon. tag set in Southeast face utility pole, above found nail.
- Az 150° 60.2' to centerline of stump at ground surface.
- AZ 160° 74.48' set mag nail with Lapeer remon. tag in West face of 23" Maple, above found nail.
- AZ 215° 70.55' set mag nail with Lapeer remon tag in East face of 34" Maple, below found nail.
- AZ 340° 73.20' found double head nail in East of 48" Maple.
- AZ 355° 172.31' set mag nail with Lapeer remon tag in East face of utility pole.
- South 68.74 to M-9, T8N, R11E
- North 2649.74 to A-8 South 2638.26 to A-10

Signed by *S Shelby W Money*  
Surveyor's Michigan License No 30092



APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 2 197  
DATE 12-2-99