

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Lapeer (County), Located In: Goodland Twp., Corner Code #: K-7, and a table for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

RECEIVED FOR RECORD 99 DEC 14 AM 9:12

Melissa DeVaugh REGISTER OF DEEDS LAPEER COUNTY MICHIGAN

511

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

A B C D E F G H I J K L M

Grid table with 13 rows and 6 columns, containing numbers 1-36.

I, Earl E. Gravlin, in a field survey on July 22 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1824 Lyon, set post, b ash 18 S13E 12, b ash 9 N20E 12. County Surveyor: nothing. 1996 Gravlin L11 P804, find 1/2" iron 5' +/- W of rd cl, W 32.23' S side nail fnc post, N30W 141.25' nail pp, N45E 40.75' SW cor tele ped. 1997 Gravlin L12 P98, find 1/2" iron 5' +/- W of rd cl, West 32.23' S side nail fnc post, N30W 141.25' nail power pole, N45E 40.75' SW cor tele ped. 1998 Rowe L13 P97, find 1/2" rerod, N70W 10.15' S edge S leg arrow sign, S35W 28.49' set PK nail top S end 24" CMP, N70E 45.89' S edge stop sign post, S25E 109.92' set nail WSW face twin 12" elm, N80W 17.71' set PK nail top N end 24" CMP. 1998 Gravlin job #980180, find 1/2" iron 5' +/- W of rd cl, West 32.23' S side nail fnc post, N30W 141.25' nail power pole, N45E 40.75' SW cor tele ped. 1998 Powell L6 P175 Act 74, same as L13 P97.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron 5' +/- W of centerline witnesses match above surveys fence to West gravel road to East K-7 to L-7 2621.53' K-7 to K-8 2652.44'

PEER GROUP APPROVED LAND CORNER PA 245 OF 1990 LAPEER COUNTY



RAY DAVIS P.S. CO. SURVEYOR DATE 10-21-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 section corner common to sections 13, 14, 23, 24 Set standard brass cap on 1/2" rod S83E 180.49' nail and tag North side 5" apple S18E 109.91' nail and tag West side 18" elm N79E 132.11' nail and tag South side 12" elm N88W 32.17' nail and tag South side fence post N22W 141.21' nail and tag West side power pole

Signed by [Signature] Surveyor's Michigan License No. 23510

Date DEC 3, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1977

REVISED MAY 14, 1977 REVISED JAN. 1981 ADAPTED FOR WORD PROCESSING MARCH, 1991