

SURVEY &
REMONUMENTATION

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:12

| | | |
|---------------------------------------|---|-----------------------------|
| <u>Lapeer</u> (County) | Located In: Goodland Twp. | Corner Code # <u>R-8</u> |
| 1. Public Land Survey | T <u>8N</u> R <u>12E</u> | <u>R-8</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Melissa DeVaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

512

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

| | | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|--|--|--|--|--|--|--|--|
| 1 | | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | | |
| 5 | | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | | |
| 7 | | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | | |
| 9 | | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | | |
| 11 | | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | | |
| 13 | | | | | | | | | | | | | | |

I, Earl E. Gravlin, in a field survey on July 22 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: 1824 Lyon, post at 40 chains, beech 18 S57W 37, ironwood 4 N70E 6. County Surveyor: nothing. 1996 Gravlin L11 P804, set 1/2" iron, E 60.0' light pole, S45E 43.18' wood post, N70E 77.70' SW cor bldg. 1997 Gravlin L12 P 98, find 1/2" iron, E 60.0' light pole, S45E 43.16' wood post, N70E 77.70' SW cor bldg. 1997 Rowe L12 P590, find 1/2" iron, E 60.0' l pole, N70E 77.70' SW cor bldg, N20E 51.11' nail cor post, S80W 39.26' S sign post. 1997 Kay job #97-20, find 1/2" iron, East 33.00' 1/2" iron, N45W 31.60' 1/2" iron, S45W 43.10' spike pp, East 60.0' spike pp. 1998 Rowe L13 P97, find 1/2" rerod, East 60.00' find nail N face light pole, S30W 43.16' find nail N face fnc cor post, N75E 110.41' SW cor blk add to church, N50W 75.97' set PK nail NE face pp. 1998 Gravlin job #980180, find 1/2" iron, E 60.0' light pole, S45E 42.16' wood post, N70E 77.70' SW cor bldg. 1998 Powell L6 P175 Act 74, find 1/2" rerod & cap unreadable, E 60.00' find nail N face light pole, S30W 43.16' find nail N face fnc cor post, N75E 110.41' SW cor blk add to church, N50W 75.97' set PK NE face PP.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner
Found 1/2" iron
4' +/- West of centerline of gravel road North South
6' South of centerline of gravel road East West
Witnesses match above surveys except post is gone
K-8 to K-7 2652.44'
K-8 to K-9 2635.47'
K-8 to L-8 2720.27'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-8 quarter corner common to sections 23 and 24
Set standard brass cap on 1/2" iron
N65E 77.63' Southwest corner church
East 59.97' nail and tag North side light pole
S23E 127.42' nail and tag West side 48" maple
S13W 100.84' nail and tag East side 8" apple
N34W 75.84' nail and tag West side power pole
N16E 104.69' nail and tag West side 16" ash

DEER GROUP
APPROVED LAND CORNER
10-21-99
DEC 3, 1999

Signed by [Signature] Date DEC 3, 1999
Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971

REVISED MAY 24, 1975
REVISED JAN. 1982
ADAPTED FOR WORD PROCESSING, MARCH, 1993