

SURVEY & 10-21
REMONUMENTATION

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:13

<u>Lapeer</u> (County)	Located In: Goodland Twp.	Corner Code # <u>L-7</u>
1. Public Land Survey	T 8N R 12E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Melissa [Signature]
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

514

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Earl E. Gravlin, in a field survey on July 22 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: 1824 Lyon, set post on split at 39.41 chains, w ash 10 N32 E 23, birch 11 S04W 12. County Surveyor: nothing. 1998 Gravlin L13 P58, set 1/2" iron on line at occupation to north and on cl of road as traveled, N55W 43.81' nail S side 20" ash, N70E 83.85' nail N side 12" hickory, S65W 72.82' nail N side 7" hickory. Unrecorded surveys: none. Act 74: none.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found iron in gravel road
Witnesses match L13 P58.
L-7 to K-7 2621.53'
L-7 to M-7 2665.50'
L-7 to L-8 2646.35'

PEER GROUP
APPROVED LAND CORNER
PA 245 OF 1990
LAPEER COUNTY

[Signature]
RAY DAVIS P.S. CO. SURVEYOR
DATE 10-21-99



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-7 Quarter corner common to sections 13, 24
Set standard brass cap on 1/2" iron
N54W 43.63' nail and tag South side 6" black ash
N01E 28.55' nail and tag West side fence post
N74E 83.71' nail and tag North side 7" hickory
S46E 42.15' nail and tag South side 7" apple
S50W 33.68' nail and tag West side 8" elm
S72W 72.70' nail and tag North side 6" Hickory

Signed by [Signature] Date DEC 3, 1999
Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971.
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993