

MAR 23 2000

REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:14

<u>Lapeer</u> (County)	Located in: Goodland Twp.	Corner Code # <u>L-8</u>
1. Public Land Survey	T 8N R 12E	<u>L-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa ...
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN
515
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Earl E. Gravlin, in a field survey on July 22 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: not set. County Surveyor: nothing. 1997 Gravlin L12 P98, set 1/2" iron at fnc int E-W & S, E 27.40' 18" triple ash, S 3.85' 15" ash, S80W 13.05' 12" ash. 1997 Rowe L12 P590, fnd 1/2" iron, E 27.4' 18" ash, S 3.85' 15" ash, S80W 13.05' 12" ash. 1998 Rowe L13 P97, fnd 1/2" iron, E 27.40' 18" triple ash, S 3.85' 15" ash, S80W 13.05' 12" ash. Unrecorded surveys: none. Act 74: none.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Iron at fence intersection East West and South
Witnesses match L12 P98
L-8 to K-8 2620.27', Rowe 2620.06'
L-8 to L-7 2646.35'
L-8 to L-9 2636.83', Rowe 2636.49'
L-8 to M-8 2637.27'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-8 Center of section 24
Set standard brass cap on 1/2" iron
East 28.42' nail and tag 18" triple ash
South 3.85' nail and tag 15" ash
S70W 13.05' nail and tag 12" ash
N30E 16.31' nail and tag 12" ash

PEER GROUP
APPROVED LAND CORNER
PA 245 OF 1990
LAPEER COUNTY
RAY DAVIS P.S. CO. SURVEYOR
DATE 10-21-99

Signed by [Signature] Date DEC 3 1999
Surveyor's Michigan License No. 23510

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 1A, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993