

SURVEY &
REMONUMENTATION

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

RECEIVED FOR RECORD

99 DEC 14 AM 9:14

For corners in

<u>Lapeer</u> (County)	Located In: Goodland Twp.	Corner Code # <u>L-9</u>
1. Public Land Survey	T <u>8N</u> R <u>12E</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa DeVaugh
REGISTER OF DEEDS
LAFAYETTE COUNTY, MICHIGAN

516

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 22 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO: 1824 Lyon, set post on split at 39.41 chains, sugar 6 N23E 9, Sugar 14 S29E 26. County Surveyor: nothing. 1973 Ciemochowski L2 P365 Act 74, 1/2" iron, N20E 27.70' PK & cap in 14" tree, S55E 45.85' PK & cap in 30" tree, S10W 24.20' PK & cap in 10" tree. 1997 Rowe L12 P590, find 1/2" iron, N25E 27.26' nail 24" maple, S05W 23.82' nail 18" walnut, S35E 35.73' PK 8" elm, N 109.23' PK 30" oak. 1997 Kay job #97-20, find 1/2" steel stake, South 23.80' spike 12" ash, North 26.80' tele box, N20E 27.25' spike 20" oak.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" iron in gravel road witnesses match above surveys.
L-9 to M-9 2603.69'
L-9 to K-9 2609.61' Rowe 2609.64'
L-9 to L-8 2636.83'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-9 quarter corner common to sections 24, 25
set standard brass cap on 1/2" iron
North 109.21' nail and tag in East side 30" oak
N28E 28.01' nail and tag in East side 20" maple
N82E 148.24' nail and tag in South side 38" oak
S62E 47.51' nail and tag in North side 36" oak
S07W 24.56' nail and tag in East side 14" oak
S75W 72.08' nail and tag in North side 12" elm

PEER GROUP
APPROVED LAND CORNER
PAGE 5 OF 1990
LAFAYETTE COUNTY

RAY DAVIS P.S. CO. SURVEYOR
DATE 10-21-99

Signed by [Signature] Date 12-2-99
Surveyor's Michigan License No. 23510