

MAR 23 2000

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

RECEIVED FOR RECORD

99 DEC 14 AM 9:14

<u>Lapeer</u> (County)	Located In: Goodland Twp.	Corner Code # <u>M-8</u>
1. Public Land Survey	T <u>8N</u> R <u>12E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Melissa Savvaugh
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

518

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1						
2	6	5	4	3	2	1
3						
4	7	8	9	10	11	12
5						
6	18	17	16	15	14	13
7						
8	19	20	21	22	23	24
9						
10	30	29	28	27	26	25
11						
12	31	32	33	34	35	36
13						

I, Earl E. Gravlin, in a field survey on July 22 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and ranges, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 1822 Wampler, N 40 chains 1/2 mile post, maple 12 N61 1/2 W 17, elm 24 S10W 15. County Surveyor: nothing. 1998 Gravlin, L13 P58, set 1/2" iron 33' East of found right of way iron, N80W 30.61' nail N side 8" tamarack, N20E 60.12' nail W side 48" maple, S80W 30.01' nail N side 8" maple, West 33.00' 1/2" iron, South 92.64' to W 1/4 cor sec 19 T8N-R13E. Unrecorded surveys: none. Act 74: none.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron in gravel road
witnesses match L13 P58
M-8 to M-7 2633.27'
M-8 to L-8 2637.27'
M-8 to M-9 2640.79'

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1990
LAPEER COUNTY



RAY DAVIS P.S. CO. SURVEYOR
DATE 11-10-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 East quarter corner section 24
set standard brass cap on 1/2" iron
S80W 29.90' nail and tag North side 8" maple
West 33.00' 1/2" iron
N64W 30.49' nail and tag North side 8" tamarack
N21E 60.08' nail and tag Northwest side 30" maple
N13E 98.64' nail and tag West side 40" oak

Signed by [Signature]
Surveyor's Michigan License No. 23510

Date DEC 3, 1999

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993