

# SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

For corners in

LAPEER

(County)

Located In:

GOODLAND TOWNSHIP

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>12E</u>	<u>M-9</u>
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

95 DEC 28 PM 2:41

LIBER NO. 005 PAGE 328

REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James T. Bailey, in a field survey on December 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1. G.L.O. (1822) WAMPLER D.S. SET POST NO WITNESSES FOUND
2. SURVEY (6/28/71) KAY P.S. UNRECORDED NO OBJECT STATED

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


1995 JAMES T. BAILEY P.S. FOUND 1/2" ROD IN THE INTERSECTION OF CADE ROAD (GRAVEL) AND TURNER ROAD (GRAVEL). WITNESSES FROM ITEM #2 ABOVE MATCH.

PEEB BROTHERS  
 APPROVED LAND CORNER  
 PAID BY THE  
 LAPEER COUNTY  
  
 RAY DAVIS P.S. CO. SURVEYOR  
 DATE 7-13-95

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-9 SET STANDARD LAPEER COUNTY REMONUMENTATION CAP ON FOUND 1/2" IRON.

- S.80°E. 43.04 SET PK NAIL W/ REMON TAG IN TELE. POLE
- S.60°W. 55.78 SET PK NAIL W/REMON TAG IN TWIN 10" ELM
- S.80°W. 59.76 SET PK NAIL W/ REMON TAG IN 22" ELM
- N.50°W. 43.55 SET PK NAIL W/ REMON TAG IN FENCE POST



Signed by 

Date DECEMBER 20, 1995

Surveyor's Michigan License No. 33968

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983