

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Lapeer

(County)	Located In:	Corner Code - #
1. Public Land Survey	T 5N R 9E	M12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on March 09, 1992, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:


M12: Post established by U.S. Deputy Surveyor J. Mampler in 1822 - accessories: Sugar 9, N78-1/2W 60 and White Oak 30, S45W 49. Line re-run by U.S. Deputy Surveyor H. Parke in 1834 - gives same accessories. Corner recorded under Act 74, PA 1970 by L. Bates (LLS #16699) in 1978 in Liber 3, Page 380 as "set 1/2" iron rod half way between northeast and southeast corners of Section 36 - accessories: N5E 10.11', 4" Cherry; N50W 27.12', 10" Oak; S30W 33.09', 18" Maple."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M12: Found L. Bates corner as recorded to be 15.68' north of midpoint in old fence line. Did not accept this iron as the corner. Reestablished corner equidistant between corners M13 and M11 in old fence line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M12: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Table
 S2E 17.84', N&T in East face 10" Poplar
 N48E 21.25', N&T in NW face 8" Poplar
 N6E 17.61', N&T in West face 6" Poplar
 S50W 20.70', N&T in SE face 20" Oak
 N1W 15.68', 1/2" iron rod



Signed by

Gary C. Bilow

Date

5/11/92