

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
1995 REMONUMENTATION PROGRAM

RECEIVED FOR RECORD

For corners in MARATHON TWP.

LAPEER  
(County)

Located In:

Corner Code #

95 DEC 13 AM 8:52

LIBER NO. 5 PAGE NO. 313  
*Helen D. Brough*  
REGISTER OF DEEDS  
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1. Public Land Survey	T	09N	R	09E	M-4
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on MARCH 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1852 GLO; WAMPLER, D.S.; SET 1/2 MILE POST; BEECH 17 S54W 10LKS., BEECH 7 N15W 31LKS.
- 1906 SICKLESTEEL, C.S.; SURVEY OF SEC.12; STAKE; PINE STUMP 40 N44W 79LKS., PINE STUMP 30 S14E 106LKS.
- 1979 BECK-GRAVLIN; BECK, P.S.#21559; SURVEY L.5, PG.596-599; SET 1/2" IRON; S54W 72.1' MSHD TAG IN P.POLE, S71E 12.18' IRON IN MON BOX SET BY MSHD, N89E 34.82' W. FACE T.POLE
- 1979 BECK, P.S.#21559; LCRC; L.3, PG.558; SET 1/2" IRON BY SINGLE PROPORTIONATE MEASURE; SAME WITS AS 1979 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD W/CAP #21559 IN C/L GRAVEL ROAD N-S, NO APPARENT OCCUPATION TO W.

G.L.O. NOTES FOR T9N-R10E INDICATE THAT THIS CORNER IS NOT COMMON WITH A-3 T9N-R10E

APPROVED LAND CORNER  
PA 345 OF 1990  
LAPEER COUNTY

M-4 TO M-3 2632.60' (BECK 1979)  
M-4 TO M-5 2632.60' (BECK 1979)

RAY DAVIS F.S.CO. SURVEYOR  
DATE 8-31-95

ACCEPTED FND ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-4 REPLACED FND ROD WITH 1/2"X 18" ROD W/ STANDARD BRASS CAP
- S55°W, 72.09' SET P-K NAIL W/REMON TAG ABOVE FND BENT NAIL W/ MSHD TAG IN SE FACE P.POLE
- S60°W, 54.00' SET NAIL W/REMON TAG IN SE FACE 12" SCOTCH PINE
- S30°E, 84.09' FND NAIL W/FLAG. IN SE FACE 10" WALNUT
- N85°E, 35.11' SET P-K NAIL W/REMON TAG IN N. FACE P.POLE
- N25°E, 53.80' SET NAIL W/REMON TAG IN NW FACE 8" ELM
- S60°E, 8.89' FND 1/4" ROD (BADLY CORRODED)
- S71°E, 12.18' FND 1/2" ROD



Signed by *Jonathan M. Field*  
Surveyor's Michigan License No. 37276

Date 12-1-95