

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PM 2:04
LIBER NO. 05 FILE NO. 180
Richard L. Smith
REGISTERED SURVEYOR
LAPPEER, MICHIGAN

For corners in	MARATHON TWP.	Located in:	Corner Code #
LAPPEER	(County)		
1. Public Land Survey	T 09N R 09E		M-7
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1852 GLO; WAMPLER, D.S.; SET POST; MAPLE 12 N22W 15LKS., MAPLE 14 S82W 19 1/2LKS.
1906 SICKLESTEEL, C.S.; STAKE; PINE 30 N89W 139LKS., PINE 36 N58E 200LKS., PINE 24 S50W 152LKS., PINE 28 N52E 39LKS.
1973 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY L.2, PG.178; IRON STAKE; S20°W 26.02' P.P., S70°E 69.37' 15" MAPLE, N40°W 93.33' P.P
1976 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY L.3, PG.761; END. IRON; SAME WITS AS 1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG.; FIELD, P.S.#37276; FND 1/2" ROD; 30' W. OF C/L GRAVEL RD N-S & ON C/L GRAVEL RD TO W. RECOVERED 3 PREVIOUS WITNESSES INDICATING THAT FND ROD IS IN SAME POSITION AS 1973 HENDERSON-BATES SURVEY GLO NOTES FOR T9N-R10E INDICATE THAT A-7 WAS SET 2.22 CH. N. OF M-7 T9N-R9E

2658.95' M-7 TO M-8 (MEAS. BY OTHERS)
2618.59' M-7 TO M-6 (MEAS. BY OTHERS)

ACCEPTED 1/2" ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessones established to perpetuate locating the position of the corner:
M-7 SET STANDARD BRASS CAP ON 1/2" ROD
S20°W, 25.98' FND NAIL W/FLAG. IN SE FACE T. POLE
S70°E, 69.34' FND NAIL W/DISK IN SW FACE 14" MAPLE
N40°W, 93.32' FND NAIL W/FLAG. IN NE FACE P. POLE
N70°E, 92.44' SET NAIL W/ REMON TAG IN NW FACE 40" OAK
NORTH, 130.47' FND 1/2" ROD W/ BROKEN CAP

PEER GROUP APPROVED LAND CORNER

PA 343 OF 1890
Signed by Jonathan M. Field
Surveyor's Michigan License No. 37276

Date 12-8-94

RAY DAVIS P.S. CO. SURVEYOR
DATE 12-22-94

