

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**1994 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

94 DEC 22 PM 2:05

LIBER NO. 05 FILE NO. 182

Hiltra D. Daugh
REGISTER OF DEEDS
LAPPEER COUNTY, MICHIGAN

For corners in	MARATHON TWP.	Located in:	Corner Code #
LAPPEER	(County)		
1. Public Land Survey		T 09N R 09E	M-9
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, JONATHAN M. FIELD, in a field survey on SEPTEMBER 23 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
1852 GLO; WAMPLER, D.S.; SET POST; BEECH 7 N25 1/2W 13 1/2LKS, BEECH 10 S44W 22LKS.
1906 SICKLESTEEL, C.S.; STAKE; PINE 36 S20E 83LKS., PINE 34 S70W 28LKS.
1978 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.4, PG.546; NO OBJECT STATED; WEST 33.61' 10" OAK, NORTH 77.22' END T-IRON, S45°W 29.88' 6" HICKORY, N20°E 55.95' 4" OAK
1980 BECK-GRAVLIN; BECK, P.S.#21559; SURVEY L.5, PG.913; 1/2" IRON; SAME WITS AS 1978 SURVEY
1985 GRAVLIN, P.S.#23510; SURVEY L.6, PG.945; END 1/2" IRON; EAST 27.85' 6" POPLAR, S50°W 29.75' 10" HICKORY, N85°W 33.34' 10" OAK
1987 GRAVLIN, P.S.#23510; LCRC L.4, PG.233; END 1/2" IRON; SAME WITS AS 1985 SURVEY ABOVE
1988 GRAVLIN, P.S.#23510; SURVEY L.7, PG.887; NO OBJECT STATED; SAME WITS AS 1978 SURVEY
1993 HENDERSON-BATES; ELRICH, P.S.#18986; SURVEY L.10, PG.387; END 1/2" IRON; EAST 27.85' 6" POPLAR, S50°W 29.75' 10" HICKORY, N15°E 78.52' UTILITY POLE, S20°E 64.93' 6" POPLAR
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 ROWE ENG.; FIELD, P.S.#37276; END 1/2" ROD (BENT & TWISTED) @ C/L GRAVEL ROAD N-S & ON LINE W/ FE ROW TO W. RECOVERED 4 PREVIOUS WITNESSES INDICATING END ROD IS IN SAME POSITION AS 1978 BECK-GRAVLIN SURVEY GLO NOTES OF T9N-R10E INDICATE THAT A-9 WAS SET 1.19 CH. N. OF M-9 T9N-R9E

2628.50' M-9 TO M-8 (MEAS. BY OTHERS)

ACCEPTED 1/2" ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9 REMOVED BENT ROD, SET NEW 1/2" ROD W/ STANDARD BRASS CAP
WEST, 33.62' SET NAIL W/ REMON TAG IN S. FACE 14" OAK
S45°W, 29.84' END NAIL W/FLAG. IN NW FACE 8" HICKORY
EAST, 27.75' END NAIL W/FLAG. IN W. FACE 6" POPLAR
N30°E, 55.87' END NAIL W/FLAG. IN W. FACE 6" OAK
N20°E, 78.44' END NAIL W/FLAG. IN E. FACE P.POLE
S20°E, 64.97' SET NAIL W/ REMON TAG ABOVE END NAIL W/FLAG. IN W. FACE 8" POPLAR
NORTH, 77.22' END T-IRON

PEER GROUP
APPROVED LAND CORNER
PA 345 OF 1000


Signature: *Jonathan M. Field*
Surveyor's Michigan License No. 37276

Date: 12-8-94

RAY DAVIS P.S. CO. SURVEYOR

LIBER 0005 PAGE 0182

DATE: 12-22-94



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN 26 1971
REVISED MAY 1987
ADAPTED FOR WORD PROCESSING MARCH 1993