

**SURVEY & REMONUMENTATION**

MAY 28 1997

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED RECORD  
 96 DEC 27 PM 1:21

For corners in DEERFIELD TWP.

Lapeer Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 09N R 10E \_\_\_\_\_ A-1 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

*Melissa De Vough*  
 REGISTER OF DEEDS  
 LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, JONATHAN M. FIELD, in a field survey on AUGUST 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1833 GLO; PARKE, D.S.; SET POST; BEECH 20 N31W 17LKS., SUGAR 20 N88E 29LKS., BEECH S80E 13LKS., SUGAR 20 S8W 14LKS.
  - 1974 HENDERSON, P.S.#16043; SURVEY L.003, PG.011; FND T-IRON; S30W 52.53' 38" OAK, S45W 46.08' T.POLE, N30W 46.70' FE COR POST
  - 1974 HENDERSON, P.S.#16043; LCRC L.002, PG.675; FND T-IRON; SAME WITS AS 1974 SURVEY ABOVE
  - 1977 BECK-GRAVLIN; GRAVLIN, P.S.#23510; SURVEY L.004, PG.152; NO OBJECT STATED; N45W 47.2' COR POST, N40E 44.05' ROAD SIGN, S55W 46.12' NAIL IN T.POLE
  - 1985 ELRICH, P.S.#18986; SURVEY L.007, PG.057; FND T-IRON; N45W 46.9' NAIL IN COR POST, S25W 52.47' NAIL 30" OAK
  - 1994 EMERY, P.S.#24593; TUSCOLA CO. REMONUMENTATION LCRC PG.50 WATERTOWN TWP. T10N-R9E; FND T-IRON; N40E 43.53' 1/2" ROD, S30E 50.40' NOTCH IN E. END 12" CMP, S30W 52.72' REMON TAG IN 40" OAK, N42W 47.77' 1/2" ROD

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996 ROWE ENG.; FIELD, P.S.#37276; FND. TUSCOLA CO. MONUMENT AND ALL 4 1994 WITNESSES

- A-1 TO M-12 T10N-R9E 2645.24'
- A-1 TO B-13 T10N-R10E 1887.65'
- A-1 TO A-2 T9N-R10E 3504.07'
- A-1 TO M-2 T9N-R9E 3775.06'
- A-1 TO L-1 T9N-R9E 2707.19' (HENDERSON-BATES 1974)
- A-1 TO L-13 T10N-R9E 2642.86' (EMERY 1994 REMON)

PEER GROUP  
 APPROVED LAND CORNER  
 PA 345 OF 1990  
 LAPEER COUNTY

*Ray Davis*  
 RAY DAVIS P.S. CO. SURVEYOR  
 DATE 8-27-96

ACCEPTED FND. TUSCOLA CO. MONUMENT AS BEST EVIDENCE OF ORIGINAL CORNER POSITION.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-1 FND TUSCOLA CO. MONUMENT
  - N40°E, 43.53' 1/2" ROD W/O CAP
  - S30°E, 50.40' NOTCH IN TOP OF E. END 12" CMP
  - S30°W 52.72' NAIL W/REMON TAG IN E. FACE 40" OAK
  - N42°W, 47.77' 1/2" ROD W/O CAP

NOTE: THIS CORNER IS COMMON WITH A-13 T10N-R10E, M-13 T10N-R9E, & M-1 T9N-R9E

Signed by *Jonathan M. Field* Date 12-2-96  
 Surveyor's Michigan License No. 37276

