

MAY 28 1997

1996 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED RECORD

96 DEC 27 PM 1:17

Melissa DeVaugh  
REGISTER OF DEEDS  
LAPPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

For corners in DEERFIELD TWP.

LAPPEER Located In: Corner Code #  
(County)

1. Public Land Survey T 09N R 10E A-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on AUGUST 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLOBURNHAM, D.S.; SET POST; BEECH 14 S34E 34LKS., BEECH 7 N43E 9LKS.  
1991 GRAVLIN, P.S.#23510; SURVEY L.009, PG.668; FND MONUMENT BOX; N45W 35.11' 8" APPLE, S40W 45.68' 24" ELM, S60E 34.11' 6" OAK  
1991 GRAVLIN, P.S.#23510; SURVEY L.009, PG.926; FND MONUMENT BOX; SAME WITS AS 1991 SURVEY ABOVE

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

PEER GROUP  
APPROVED LAND CORNER  
PA 345 OF 1990  
LAPPEER COUNTY

RAY DAVIS P.S. CO. SURVEYOR  
DATE 8-27-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 ROWE ENG.; FIELD, P.S.#37276; FND. 1/2" ROD IN MONUMENT BOX 5' W. OF C/L WILLITS ROAD (GRAVEL TO N. ASPH. TO S.) & ON APPROX. C/L EXTENDED OF OTTER LAKE ROAD TO E.  
RECOVERED 2 REMAINING WITNESSES OF 1991 SURVEY CITED ABOVE INDICATING FND ROD IS IN SAME POSITION AS 1991 SURVEY

A-3 TO A-2 2651.24'  
A-3 TO A-4 2675.64'

ACCEPTED FND. ROD AS BEST EVIDENCE OF ORIGINAL CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-3 SET STANDARD REMON CAP ON FND 1/2" ROD IN MON. BOX  
N45°W, 35.21' FND. NAIL IN S. FACE 8" APPLE  
N30°E, 56.83' P-K NAIL IN S. END 12" CMP  
S40°W, 45.64' FND. NAIL IN SE FACE 24" ELM  
S30°E, 70.74' P-K NAIL IN N. END 12" CMP  
S35°W, 49.29' NAIL W/TAG #37276 IN E. FACE 10" APPLE



Signed by Jonathan M. Field Date 12-2-96  
Surveyor's Michigan License No. 37276