

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 NOV 12 PM 2:41

For corners in: **DEERFIELD TWP.**

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>09N</u> R <u>10E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Melissa De Vaughn
REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO; BURNHAM, D.S.; SET POST; BEECH 12 S60E 55LKS., BEECH 10 N23E 63LKS.
1979 KENNEDY SURVEYING; KENNEDY, P.S.#17623; SURVEY; L.005,PG.85-86; FND. 1" PIPE; N20E 65.32' P/POLE, N70W 73.06' P.POLE, S80E 167.01' 24" MAPLE

A-5 TO A-4 2607.27 REI '97

A-5 TO M-5 215.16' G.L.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 ROWE; FIELD, PS#37276; FND. 3/4" PIPE IN MON BOX AT C/L-C/L GRAVEL ROADS N-S-E

RECORDED
LAPEER COUNTY, MICHIGAN
JONATHAN M. FIELD
REGISTERED PROFESSIONAL SURVEYOR
DATE 9-29-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 1/2" ROD W/ STANDARD REMON CAP SET INSIDE 3/4" PIPE
SOUTH, 222.15' 1/2" ROD W/ REMON CAP AT M-5 T9N-R9E
N26°E, 65.26' P-K NAIL W/ REMON TAG IN SE FACE T.POLE
N36°W, 33.74' NAIL W/ REMON TAG IN SW FACE 10" MAPLE
N49°W, 72.96' NAIL W/ TAG #17623 IN NE FACE P.POLE
S50°W, 29.36' 1/2" ROD W/ CAP #37276
S36°E, 25.00' 1/2" ROD W/ CAP #37276

Signed by Jonathan M. Field Date 11-11-97
Surveyor's Michigan License No. 37276



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1974

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993