

SURVEY & REMONUMENTATION

MAR 13 1998

SECTION

**1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 NOV 12 PM 2:46

Melissa DeVaugh
**REGISTER OF DEEDS
LAPEER COUNTY, MICHIGAN**

Register of Deeds Stamp & File Number

For corners in: **DEERFIELD TWP.**

<u>LAPEER</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>09N</u> R <u>10E</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1834 GLO; BURNHAM, D.S.; NOT SET DURING ORIGINAL GOVERNMENT SURVEY
1972 FLINT SURVEYING; CARLSON, P.S.#9189; SURVEY; L.001,PG.582; NO OBJECT STATED; EAST 26.26' FEN. POST, S45W 114.12' NE COR. HOUSE #4739, S30E 110.25' P.POLE
1973 HENDERSON-BATES; HENDERSON, P.S.#16043; SURVEY; L.002,PG.005; FND. 1/2" ROD; SAME WITS AS 1972 SURVEY ABOVE
1974 GIFFELS-WEBSTER; PAWLACZYK, P.S.#17632; SURVEY; L.002,PG.559-563; FND. 1/2" ROD; SAME WITS AS 1972 SURVEY ABOVE
1974 GIFFELS-WEBSTER; PAWLACZYK, P.S.#17632; SURVEY; L.002,PG.615-617; 1/2" ROD; SAME WITS AS 1972 SURVEY ABOVE
1985 GRAVLIN, P.S.#23510; SURVEY; L.007,PG.085; FND. 1/2" IRON; SAME WITS AS 1972 SURVEY ABOVE

A-10 TO A-9 2697.94' G.W.E. '74 2698.02' REI '97
A-10 TO A-11 2611.47' HENDERSON-BATES '73 2611.64' REI '97
A-10 TO M-10 58.74' AVG. G.L.O.
A-10 TO B-10 2044.87' G.W.E. '74

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1/2" ROD 2' W. OF C/L GRAVEL ROAD N-S & ON OCCUPIED TREE LINE TO E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-10 1/2" ROD W/ STANDARD REMON CAP
S20°E, 110.10 NAIL W/ REMON. TAG IN NE FACE T.POLE
S50°W, 114.12' NE CORNER CONC. BLOCK FOUNDATION
S40°W, 26.79' PUNCH HOLE IN S. END 12" CMP
N85°W, 18.07' PUNCH HOLE IN N. END 12" CMP
N20°E, 81.39' NAIL W/ REMON TAG IN W. FACE 8" OAK
EAST, 62.22' NAIL W/REMON TAG IN S. FACE TWIN 6" OAK
EAST, 33.00' FND. 1/2" ROD W/ BROKEN CAP
SOUTH, 21.58' FND. 1/2" ROD W/ REMON CAP AT M-10 T9N-R9E



Signed by Jonathan M. Field Date 11-11-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993

FEB 1998
APPROVED LAND CORNER
PAGE 45 OF 180
LAPEER COUNTY

LIBER0005 PAGE0444

Ray Davis
RAY DAVIS, P.S. CO. SURVEYOR
DATE 9-29-97

9