

MAR 29 1999

SECTION

1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: DEERFIELD TWP.

LAPEER  
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD

98 DEC 22 PM 3:45

*Helisa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

426

- 1. Public Land Survey T 09N R 10E  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

E-1  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1834 GLO; BURNHAM, D.S.; INTERSECTED N BNDY 2CH 92LKS E; SUGAR 28 S34E 47 LKS, BEECH 14 S15W 45 LKS.  
1906 SICKLESTEEL, C.S.; SURVEY SEC. 5, T9N-R10E; PG.8-9; STAKE; APPLE 2 S38E 75LKS, APPLE 2 S55E 97LKS.  
1972 HENDERSON, P.S.#16043; SURVEY L.001, PG.736; FND. 3/4" PIPE; S60°E 75.73' P.POLE, S60°W 117.41' P.POLE, N70°W 104.80' P.POLE  
1972 HENDERSON, P.S.#16043; LCRC L.001, PG.553-4; FND. 3/4" PIPE; SAME WITS AS 1972 SURVEY ABOVE  
1974 ELRICH, P.S.#18986; SURVEY L.002, PG.873; FND. 3/4" BAR; SAME WITS AS 1972 SURVEY ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND. ROD IS IN SAME POSITION AS 1972 IRON CITED IN SECTION A ABOVE

- E-1 TO E-13 192.72' (G.L.O.)  
190.90' (ROWE '98)
- E-1 TO D-1 2666.81' (ROWE '98)
- E-1 TO F-1 2636.18' (ROWE '98)

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-1 SET STD. REMON. CAP ON FND. 1/2" ROD  
S18°W, 58.50' P-K NAIL IN SW FACE P.POLE  
S60°E, 75.76' NAIL W/ TAG IN SW FACE P.POLE  
N32°E, 66.31' P-K ANIL W/ REMON TAG IN E. FACE 20" PINE  
N07°W, 106.50' SW COR. BRICK HOUSE #17

Signed by Jonathan M. Field  
Surveyor's Michigan License No. 37276

Date 10-28-98



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993