

MAR 29 1999

1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich: P.A. 1970

For corners in: DEERFIELD TWP.

RECEIVED FOR RECORD

98 DEC 22 PM 3:46

LAPEER

(County)

Located In:

Corner Code #

G-1

427

*Melissa De Vaughn*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 09N R 10E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4					3	2	1			
3													
4	7	8	9					10	11	12			
5													
6	18	17	16					15	14	13			
7													
8	19	20	21					22	23	24			
9													
10	30	29	28					27	26	25			
11													
12	31	32	33					34	35	36			
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 1834 GLO; BURNHAM, D.S.; INTERSECTED N BNDY 2CH 35LKS E; MAPLE 18 S19W 30 LKS, B.ASH 12 S21E 34 LKS.  
 1906 SICKLESTEEL, C.S.; SURVEY SEC. 3, T9N-R10E; PG.6-7; STAKE; SWAMP OAK 14 N14W 19LKS  
 1972 HENDERSON, P.S.#16043; SURVEY L.001, PG.522; SET P.K. NAIL & CAP; N10°E 19.92' GUARD RAIL POST, S45°E 24.73' GUARD RAIL POST, N40°W 30.93' 6" ELM  
 1972 HENDERSON, P.S.#16043; LCRC L.001, PG.287-8; SAME WITS AS 1972 SURVEY ABOVE  
 1974 ELRICH, P.S.#18986; SURVEY L.002, PG.873; FND. P.K. NAIL; SAME WITS AS 1972 SURVEY ABOVE  
 1976 BECK, P.S.#21559; SURVEY L.003, PG.921; FND. P.K. NAIL; N10°E 18.97' NAIL & DISC IN TOP OF POST, N70°W 95.14' NAIL S. FACE 6" MAPLE, S45°E 24.84' NAIL & DISC IN TOP OF POST  
 1979 GRAVLIN, P.S.#23510; SURVEY L.005, PG.353 FND. 1" BAR 2.5' BELOW SURFACE SET 1/2" IRON AT SURFACE; S10°E 20.27' NAIL GUARD RAIL, N15°W 20.53' NAIL GUARD RAIL, N40°W 37.68' 6" ELM  
 1990 ELRICH, P.S.#18986; SURVEY L.008, PG.680; FND. 1/2" IRON W/ CAP #23510; N35°W 37.68' 6" ELM, NORTH 33.16' 8" MAPLE, S40°E 36.5' 6" ASH  
 1990 ELRICH, P.S.#18986; LCRC L.004, PG.331; SAME WITS AS 1990 SURVEY ABOVE  
 1992 GRAVLIN, P.S.#23510; SURVEY L.009, PG.954; SAME WITS AS 1990 SURVEY ABOVE  
 1993 GRAVLIN, P.S.#23510; SURVEY L.010, PG.444; FND. 1/2" IRON; SAME WITS AS 1979 SURVEY ABOVE  
 1993 GRAVLIN, P.S.#23510; SURVEY L.010, PG.250; FND. 1/2" IRON; SAME WITS AS 1979 SURVEY ABOVE  
 1996 FIELD, P.S.#37276; LCRC (1996 REMON); L.005, PG.378; FND. 1/2" ROD; 148.57' EAST OF G-13 T10N-R10E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1990 IRON CITED IN SECTION A ABOVE

G-1 TO H-1 2605.38' (GRAVLIN '79) G-1 TO G-13 155.1' (G.L.O.)  
 2605.37' (HENDERSON-BATES '90) 148.57' (ROWE '98)  
 2605.37' (GRAVLIN '92)  
 2605.38' (ROWE '98) G-1 TO F-1 2628.60' (ROWE '98)

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 G-1 SET STD. REMON CAP ON FND. 1/2" ROD  
 N74°W, 103.90' NAIL W/ REMON. TAG IN S. FACE 36" MAPLE  
 S56°E, 55.45' NAIL W/ REMON TAG IN N. FACE 8" OAK  
 NORTH, 33.16' NAIL IN W. FACE 8" MAPLE  
 S40°E, 36.50' NAIL IN NE FACE 6" ASH

Signed by *Jonathan M. Field*  
 Surveyor's Michigan License No. 37276

*Jonathan M. Field*  
 Date 9-17-98  
 Date 10-28-98

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED MAY 14, 1975, REVISED JAN., 1983, ADAPTED FOR WORD PROCESSING MARCH, 1993