

MAR 29 1999

1998 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: DEERFIELD TWP.

LAPEER  
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD

98 DEC 22 PM 3:48

*Melissa DeVaugh*  
REGISTER OF DEEDS  
LAPEER COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 09N R 10E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- I-1
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_

428

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JUNE 30 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1834 GLO; BURNHAM, D.S.; INTERSECTED N BNDY 90LKS E; SUGAR 14 S38W 33 LKS, SUGAR 18 S39E 23 LKS.  
 1906 SICKLESTEEL, C.S.; SURVEY SEC. 2, T9N-R10E; PG.4-5; STAKE; W. OAK 40 N73 1/2E 177LKS, PINE 40 S9E 125LKS.  
 1906 SICKLESTEEL, C.S.; SURVEY SEC. 3, T9N-R10E; PG.6-7; NO OBJECT STATED; NO WITS GIVEN  
 1974 KAY, P.S.#14096; SURVEY L.003, PG.149; FND. IRON ROD; NO WITS GIVEN  
 1975 KAY, P.S.#14096; SURVEY L.003, PG.204; FND. IRON ROD; NO WITS GIVEN  
 1977 GRAVLIN, P.S.#23510; SURVEY L.004, PG.161; FND. IRON ROD; NO WITS GIVEN  
 1989 GRAVLIN, P.S.#23510; SURVEY L.008, PG.454; FND. 1/2" IRON; NORTH 24.57' 30" MAPLE, N70°W 63.57' 36" MAPLE, S75°W 97.48' 20" MAPLE  
 1991 GRAVLIN, P.S.#23510; LCRC L.004, PG.377; FND. 1/2" IRON; SAME WITS AS 1989 SURVEY ABOVE  
 1992 GRAVLIN, P.S.#23510; SURVEY L.009, PG.827-8; FND. 1/2" IRON; SAME WITS AS 1989 SURVEY ABOVE  
 1996 FIELD, P.S.#37276; LCRC (1996 REMON); L.005, PG.386; FND. 1/2" ROD IN MON BOX; 63.70' EAST OF I-13 T10N-R10E

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1998 ROWE; FIELD, PS#37276; FND. 1/2" ROD IN MON. BOX RECOVERED 1 PREVIOUS WITNESS WHICH INDICATES THAT FND. ROD IS IN SAME POSITION AS 1996 IRON CITED IN SECTION A ABOVE

- I-1 TO APPARENT H-1 2610.56' (GRAVLIN '89) I-1 TO I-13 59.4' (G.L.O.)
- 2610.40' (ROWE '98) 63.70' (ROWE '98)
- I-1 TO APPARENT J-1 2631.38' (ROWE '98)

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-1 SET STD. REMON. CAP ON FND. 1/2" ROD IN MON. BOX  
 WEST, 63.70' 1/2" ROD W/ LAPEER REMON CAP  
 S49°W, 46.70' 1/2" ROD W/ CAP #18986  
 S74°W, 56.42' NAIL W/ REMON TAG IN N. FACE 7" ELM  
 S52°E, 74.23' P-K NAIL W/ REMON TAG IN N. FACE P. POLE  
 N70°W, 99.81' NAIL W/ REMON TAG IN S. FACE 5" MAPLE

*Jonathan M. Field*  
DATE 9-17-98



Signed by Jonathan M. Field Date 10-28-98

Surveyor's Michigan License No. 37276

CA